

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19106-00-00
Spot: SESWNW Sec/Twnshp/Rge: 13-13S-19W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease Name: GATSCHET Well #: 1
County: ELLIS Total Vertical Depth: 3678 feet

Operator License No.: 3715
Op Name: S.B. OIL COMPANY
Address: 921 W 41ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3666	0	w/150 sxs cmt
SURF	8.625	195	0	

54
#119

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2005 12:30 PM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: CHARLES BRULL Company: S.B. OIL COMPANY Phone: (785) 625-2455

Proposed Plugging Method: Encountered fish at 750' - milled to 860' - cannot get any further.
Plug well while pulling unit is at location.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2005 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 800' - circulated 150 sxs cement to surface.
Tied to annulus - circulated 50 sxs cement and 150# hulls to surface through casing.
Swedged to 5 1/2" casing - squeezed with 60 sxs cement and 150# hulls.
Max. P.S.I. 600#. S.I.P. 300#.
Total of 260 sxs 60/40 pozmix - 10% gel and 300# hulls.

Perfs:

Remarks: ALLIED CEMENTING COMPANY. AMERICAN TANK-WATER.

Plugged through: TBG

District: 04

HJD

Signed Roger L. Moses
(TECHNICIAN)

RECEIVED
AUG 05 2005
KCC WICHITA

INVOICED
DATE 8-5-05
INV. NO 2006060266

Form CP-2/3

AUG 03 2005

MARTIN & KELLER

#1 GATSCHET

13-13-19W
SE SW NW

Contr. LEBEN DRLG

ELLIS

County

E 2071 KB Comm. 2/19/65 Comp. 5/6/65 IP IP 121 80PD, NW, GR

36: (IANS 3390-3558)

LOG-Tops	Depth	Datum	Casing
ANH	1170	+701	8" 195: (TOR 3334-43)
TOP	3058	--987	5" 3666/150 SX:
*HEEB	3314	--1243	DST 3334-76/1', GTS/30", TSTM, 1520' CLN GSY O, BHP 1200-1170#, FP 110-450#:
IANS	3368	--1297	DST 3378-3422/1', GTS/40", TSTM, 2280' CLN GSY O, BHP 1250-1180#/30", FP 430-830#:
B KC	3614	-1543	DST 3425-60/1', 950' GIP, 60' WTRY GSY M, 700' CLN GSY O, 440' FROGGY O, 60' W, BHP 1250-1200#/30", FP 270-510#:
MARM	3624	--1553	DST 3462-93/1', GTS/10", TSTM, 1520' CLN GSY O, BHP 1310-1170#:
			30", FP 260-570#:
ARR	3664	-1593	
RID	3678	--1607	

**TOR 3332 --1261
INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

CEOL: CHARLES SPRADLIN:

CON'T