

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03196-00-00

Spot: CNWNWNW ^N Sec/Twnshp/Rge: 13-15S-18W ^{KCC}
330 feet from S Section Line, 330 feet from E Section Line ^{SP 8-05}

Lease/Unit Name: LEIKER T S

Well Number: 1

County: ELLIS

Total Vertical Depth: 3592 feet

Operator License No.: 30762

Production Casing Size: 5.5 feet: 3580 150 SX CMT

Op Name: OIL COMPANY OF AMERICA, INC.

Surface Casing Size: 8.625 feet: 1168 550 SX CMT

Address: 1200 MAIN STE 406
HAYS, KS 67601

\$116.74

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/30/2003 12:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREW

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 405 sxs 60/40 pozmix - 10% gel - 800# hulls.
Plug at 3554'. Perfs 3306'-3310'; 3328'-3336'; 3462'-3472'.
Hole in 5 1/2" between 1370' and 1390'.
Casing parted.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/30/2003 4:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing ran wireline in hole to 950'.
Tied onto casing. Casing parted - pulled 1000' of 5 1/2" casing.
RIH with tubing to 1350' - pumped 300 sxs 60/40 pozmix with 800# hulls mixed into cement.
Pulled tubing to 400' - pumped 100 sxs 60/40 pozmix to circulate cement to surface.
POOH. Pulled tubing.
Hole was standing full of cement.

RECEIVED
MAY 05 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14707.

Plugged through: TBG

District: 04

Signed *Pat Staab*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 5-6-03

NO. 2003061499

MAY 01 2003

ALPINE OIL & ROYALTY #1 T S LEIKER 13-15-18W
NW NW NW

Contr. _____ ELLIS County

E 2019 RB Comm. _____ Comp. 4-23-54 IP 536 BOPD
PERM PMP

Tops	Depth	Datum
ANH	1154	865
HEEB	3251	-1232
LANS	3298	-1279
GONG	3564	-1545
ARB	3577	-1558
TD	3592	-1573

Casing
8" 1168
5" 3580
DST 3441-75/1 HR, 30'
MUD, SSO, BHP 0#
DD 3592: 1200' OIH/12
HR: SWB 6 BOPH/5 HR

LEIKER EAST POOL

+	+	+
+	+	+
+	+	+



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS