

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21710-00-00
Spot: SWNESW Sec/Twnshp/Rge: 30-14S-14W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: REXROAT B Well #: 3
County: RUSSELL Total Vertical Depth: 3223 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3218	0	
SURF	8.625	806	0	w/500 sxs cmt

#10475

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/29/2005 10:00 PM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO, INC.

Phone: (785) 628-6101

Proposed
Plugging
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: PARTIAL

Date/Time Plugging Completed: 07/30/2005 2:45 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

07/29/2005 - Sanded off bottom to 2992'.
Rigged up Allied Cementing - spotted 20 sxs cement with 100# hulls thru tubing at 2955'.
POOH.
Perf Tech shot casing free at 2100'. SIFN.
07/30/2005 - Pulled 5 1/2" up to 1462' - mixed and spotted 100 sxs cement with 300# hulls.
Pulled up to 822' - spotted 40 sxs cement with 100# hulls.
Pulled up to 410' - spotted 30 sxs cement with 100# hulls.
Pulled up to 158' and circulated cement with 40 sxs cement.
POOH. Topped with 5 sxs cement.

RECEIVED
AUG 04 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE


8-5-05

INVOICE NO.

2006060259

AUG 01 2005

OKMAR OIL COMPANY
 970 4TH FINANCIAL CENTER #3 "B" REXROAT 30-14-14W
 WICHITA, KS 67202 SW NE SW
 CONTR THUNDERBIRD DRLG INC CTY RUSSELL
 GEOL BOB ELDER FIELD GORHAM
 E 1802 KB CM 5/15/81 ^{CARD}ISSUED 3/10/83 IP P 30 BOPD
 ARB OH 3218-3223
 API 15-167-21,710



SMP	Tops	Depth/Datum
ANH	802 + 1000	
B ANH	836 + 966	
TOP	2692 - 890	
HEEB	2917 - 1115	
TOR	2936 - 1134	
LANS	2976 - 1174	
ARB	3211 - 1409	
RTD	3223 - 1421	

8 5/8 "806/500SX, 5 1/2 "3218
 DST (1) 2915-2953 (TOR) / 30-30-30-30, REC 10' M, SIP 97-58#, FP 54-54/54-54#
 DST (2) 2950-3005 (LANS AB) / 60-60-60-60, REC 65' DM, SIP 435-435#, FP 65-73/82-87#
 DST (3) 3030-3078 (LANS E,F,G) / 60-60-60-60, REC 160' M, SSO, SIP 336-320#, FP 65-73/73-85#
 DST (4) 3126-3175 (LANS I,J) / 30-30-30-30, REC 5' M, SIP 90-57#, FP 49-49/49-49#
 DST (5) 3204-3215 (ARB) / 30-30-30-30, REC 10' M, SSO, SIP 49-41#, FP 41-41/41-41#
 DST (6) 3204-3218 (ARB) / 30-30-30-30, REC 10' M, SIP 41-41#, FP 41-41/41-41#
 DST (7) 3204-3223 (ARB) / 60-60-60-60, REC 150' FROTHY OIL, SIP 1068-1068#, FP 41-57/82-98#
 MICT - CO, (ARB OH 3218-3223), AC 500G, SWB LD, GSO, R&T, POP, P 30 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

15700
 0918
 1MAOICEN