

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-25997-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 10-31S-15E
4780 feet from S Section Line, 3140 feet from E Section Line
Lease Name: SCOTT Well #: 10
County: MONTGOMERY Total Vertical Depth: 1430 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1430		
SURF	10	20		

#35⁰⁰

Well Type: SWD UIC Docket No: D24260.0 Date/Time to Plug: 07/11/2005 8:00 AM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed
Plugging
Method:

Run 1 inch cement string to TD and fill well from bottom to top with portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 07/12/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

1 inch cement string was run to 1300 ft inside the 2.875 inch casing. Plugging contractor began filling the well with cement but could get no return, therefore the cement string was removed and the cement allowed to set overnight. A total of 210 sacks of cement were used so far. 07-12-05: Run cement string back in well and hit cement at 750 ft. Filled well from bottom to top using a total of 238 sacks of portland cement. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

AUG 4 2005 *AMP*

CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)

RECEIVED
AUG 08 2005
KCC WICHITA

INVOICED Form CP-2/3
DATE 8-8-05
INV. NO 2006060274