

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21502-00-00
Spot: W2 Sec/Twnshp/Rge: 14-21S-23W
2670 feet from S Section Line, 1380 feet from W Section Line
Lease Name: FRUSHER EWY Well #: 1
County: HODGEMAN Total Vertical Depth: 4660 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	217		

45
#151

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/03/2005 7:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: SKIP SMITH Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 08/03/2005 9:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:


1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 60 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL.

Plugged through: DP

District: 01



Signed

Jerry W. Stapleton PART II
(TECHNICIAN)

RECEIVED
AUG 08 2005
KCC WICHITA

INVOICED
DATE 8-8-05 Form CP-2/3
INV. NO. 2006060286