

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21882-00-01
Spot: SENE Sec/Twnshp/Rge: 8-32S-15W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: MARSH Well #: 1-8
County: BARBER Total Vertical Depth: 4403 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4407	3450	WITH 150 SX CMT
SURF	8.625	418		WITH 175 SX CMT

#143¹⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2005 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4200' & 4 SX CMT. PLUG AT 900' WITH 12 SX GEL & 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2005 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4100' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 900' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4266	4268		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Gaps
(TECHNICIAN)

RECEIVED
AUG 08 2005
KCC WICHITA

INVOICED
DATE: 8-8-05
INV. NO. 2006060284