

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21432-00-00
Spot: N2SW Sec/Twnshp/Rge: 16-31S-17W
1980 feet from S Section Line, 3960 feet from E Section Line
Lease Name: GRIFFIN Well #: 2-16
County: COMANCHE Total Vertical Depth: 5165 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5165	4050	WITH 100 SX CMT
SURF	8.625	619		WITH 175 SX CMT

#167 86

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/29/2005 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK WITH 4 SX CMT OR CIBP @ 5000' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SXGEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2005 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4995' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. DID NOT HAVE RETURNS. 2ND PLUG AT 630'. ATTEMPT TO BREAK CIRCULATION WITH WATER. COULD NOT. WAIT ON HULLS & GEL. DID NOT RETURN WITH GEL. PUMPED 500# HULLS. FLUID LEVEL REMAINED AT @ APPROXIMATELY 160'. NO RETURN. PUMPED 25 SX CMT WITH 4% CC. NO RETURNS. SHUT DOWN OVER WEEKEND TO LET CMT SET. 8/1/05: RUN IN AND TAG TOC @ 630'. RUN 4 1/2" CASING BACK IN TO 620'. WAIT ON CMT. LOADED HOLE WITH 200# HULLS & 10 SX GEL. SPOT 50 SX CMT OF COMMON CEMENT. 3RD PLUG AT 40' WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
5068	5072		
5059	5064		
5049	5054		

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CEMENT BY COPELAND ACID & CEMENTING.

Plugged through: CSG

District: 0



Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG 06
KCC WICHITA

INVOICED
DATE 8-8-05
INV. NO 2006060283