

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number October 18, 1958 (of this well) (This must be listed; if no API# was issued, please note drilling completion data.)

OXY USA, Inc.

LEASE OPERATOR ~~Cities Service Oil and Gas Corp.~~ OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400
4950' FEL

LEASE (FARM) Nana NW Unit WELL NO. 201W WELL LOCATION 330' FSL CO. Graham

SEC. 32 TWP. 7S RGE 24 (W) Total Depth 3935' PLUG BACK TD 3935'

CHECK ONE:

OIL WELL GAS WELL D & A SWD OR INJ WELL INJ. DOCKET NO. 74,382-C

SURFACE CASING SIZE 8-5/8" SET AT 223' CEMENTED WITH 160 SACKS

CASING SIZE 4-1/2" SET AT 3934' CEMENTED WITH 125 SACKS

PERFORATED AT 3838-77' (2 sets)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Prognosis attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? YES

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: To be arranged.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

NAME J. D. Hininger PHONE # (913) 674-2182

ADDRESS ~~Cities Service Oil and Gas Corp.~~ OXY USA, Inc.
P.O. Box 38
Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Service Co. LICENSE NO. _____
ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT STATE CORPORATION COMMISSION SIGNED: Raymond Hill
(Operator or Agent)

MAY 25 1988 DATE: 5-24-88

MAY 25, 1988
CONSERVATION DIVISION
Wichita, Kansas

15-065-00587-00-~~100~~1

NANA NW UNIT

201W

WELL LOG

Burch Drilling Co., Inc.
1 Goff
SW SW SW 33-79-24W
Graham County, Kansas

8 5/8" set @ 223' w/ 160 ax.
ELEVATION: 2440 Kell. Bushing
COMM: 10-3-58
COMP: 10-9-58
Set 4 1/2" @ 3934' W/125 ax.

Tops

1850 Shale & Shells
2106 Shale
2139 Anhydrite
2153 Shale & Lime streaks
3726 Lime & Shale
3935 Lime

3935 Total Depth

ANHYDRITE 2107
KEENEWER 3675
TORONTO 3699
LANSING 3712

DST # 1 3738-3773 Open 1 hr.
Rec. 180' Gas plus 310' oil cut
muddy saltwater plus 380' slightly
oil gas cut muddy saltwater.
IBHP 1340#, IFF 0#, FFP 350#,
FBHP 1280#.

DST # 2 3776-3798 Open 1 hr.
Rec. 385' muddy saltwater IBHP
1415#, IFF 45#, FFP 210#, FBHP 1275#

DST # 3 3828-3870 Open 30 min.
Rec. 20' oil specked mud. IBHP 230#
IFF 0#, FFP 0#, FBHP 190#.

DST # 4 3870-3900 Open 1 hr.
REC. 30' oil plus 20' muddy oil.
IBHP 1410#, IFF 0#, FFP 0#, FBHP
1285#.

STATE OF KANSAS, COUNTY OF SEDGWICK:

I, Earl M. Burch, President of Burch Drilling Co., Inc. being duly sworn on oath,
state: That I have knowledge of the facts, statements and matters herein contained and that
the same are true and correct.

Earl M. Burch

Subscribed and sworn to before me this 6th day of November, 1958.

Lenny Harrison
Notary Public

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
AUG 26 '88
EXPIRES

May 26, 1988

WELL PLUGGING NOTICE

Nana NW Unit #201W (Inj.)
330' FSL 4950' FEL
Sec. ~~32~~-07S-24W
Graham County
33 KCC
pg 6-1-08

OXY USA, Inc.
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200