

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-047-21507-0000  
LEASE NAME Biaggi 'A'  
WELL NUMBER 2-33

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

330 Ft. from North Line of Section  
990 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION NW NE NE  
ADDRESS 8080 E. Central, Ste 300 Section 33 Township 25s Range 20w  
CITY, STATE, ZIP Wichita, Kansas 67206 County Edwards  
PHONE # 316-636-2737 Date Well Completed August 13, 2005  
Character of Well Dry and Abandoned Date Plugging Commenced August 13, 2005  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 13, 2005

The plugging proposal was approved on August 12, 2005 (date)  
by Richard Lacy (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 4723

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	85			
Sand, Gravel and Clay	Shale	85	280	8-5/8"	354	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged well with heavy mud from 4723' to 1360', then 50 sx at 1360', 50 sx at 390' and 10 sacks at 40' to surface. Plugged rathole with 15 sacks and mousehole with 10 sacks. Total cement used = 135 sacks. Used 60/40 Poz 6% Gel for plugging. Plugging completed at 4:30am on 8-13-05 by Acid Services, ticket # 10725. Received plugging orders from Richard Lacy at 3:00 pm on 8-12-05.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 18th day of August, 2005



*Pamela S. Fields*  
(Notary Public)

My Commission Expires: \_\_\_\_\_

**RECEIVED**  
**AUG 19 2005**  
**KCC WICHITA**

Form CP-4  
Revised 12-92

*Bm*

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Biaggi 'A' 2-33

**LOCATION:** NW NE NE  
**API:** 15-047-21507-0000

Section 33 T 25s R 20w  
Edwards County, Kansas

**OWNER:** McCoy Petroleum Corporation  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 08/04/05  
**COMPLETED:** 08/13/05

<b>TOTAL DEPTH:</b>	<b>DRILLER</b>	4723	<b>FEET</b>
	<b>LOGGER</b>	No Log	<b>FEET</b>

**Ground Elevation:** 2264  
**KB Elevation:** 2273

## LOG

0 -	3 FEET	Top Soil
3 -	325 FEET	Shale, Sand & Gravel, Clay
325 -	1320 FEET	Redbeds
1320 -	1363 FEET	Anhydrite (Driller's)
1363 -	2400 FEET	Shales and Salt
2400 -	4723 FEET	Limestone/Shales

## CASING RECORDS

### Surface Casing:

Spud @ 4:45 pm on 08/04/05. Drilled 12-1/4" hole to 370'. Ran 8 jts. of new 23# 8-5/8" surface casing tally 354.22' set at 365.22' KB. Cemented with 250 sx 60/40 Poz, 2% Gel, 3% CC, & 1/4 # per sx Celloflake. Plug down at 12:15 am on 08/05/05. Cement did circulate. Acid Services ticket # 10900. Welded straps on bottom 2 joints, welded collars on 6 joints.

### Plugging Data:

Plugged well with heavy mud from 4723' to 1360', then 50 sx at 1360', 50 sx at 390' and 10 sacks at 40' to surface. Plugged rathole with 15 sacks and mousehole with 10 sacks. Total cement used = 135 sacks. Used 60/40 Poz 6% Gel for plugging. Plugging completed at 4:30am on 8-13-05 by Acid Services, ticket # 10725. Received plugging orders from Richard Lacy at 3:00 pm on 8-12-05. Sterling reported plugging to KCC on 08/15/05.

## DEVIATION SURVEYS

1 degree(s) at 370 feet  
3/4 degree(s) at 4718 feet

RECEIVED  
AUG 19 2005  
KCC WICHITA