

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER. 15-065-20,914-00-00

LEASE NAME Cummings

WELL NUMBER 1-31

 Ft. from S Section Line

 Ft. from E Section Line
 C NE SE SE

SEC. 31 TWP. 7 RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 10-13-87

Plugging Completed 10-15-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Graham-Michaelis Corporation

P.O. Box 247

ADDRESS Wichita, Kansas 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4170'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	235'	none
				4-1/2"	3966'	812'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3736' and 4 sacks cement. Shot and pipe @2200', 1800', 1400', 1000', 812', pulled a total of 25 joints of 4-1/2" casing. Plugged surface with 5 sacks hulls and 200 sacks econolite.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 87

Jane Starnes
 Notary Public

My Commission Expires:



OCT 23 1987
 OCT 23 1987 Form CP-4
 CONSERVATION DIVISION Revised 07-86
 Wichita, Kansas

BELL PLUGGED RIGS
1-800-831-1111

-- INVOICE --

15-065-20914-00-00

Kelso Casing Pulling, Inc.

Post Office Box 347
CHASE, KANSAS 67524
Phone (316) 938-2457



DARRELL KELSO - President
MIKE KELSO - Vice-President

OPERATORS LICENSE NO.

Customer's
Order No. & Date

Refer To
Invoice No. 561

SOLD TO

Graham-Michaelis Corporation
P.O. Box 247
Wichita, Kansas 67201

Invoice Date 10-20-87

Lease and Well No.

Carrings 1-31 Graham County

TERMS: All purchases made on credit during the month are due and payable by the 10th of the following month. Any balance not paid by the 24th of the following month shall be subject to a FINANCE CHARGE computed at a periodic rate of 1 1/2% per month which is an ANNUAL PERCENTAGE RATE of 18%

RECEIVED
KANSAS CORP
1987 OCT 26
1987 OCT 26 11:00 AM

QUANTITY	DESCRIPTION	UNIT PRICE	AMOUNT
	Boye In Charge	\$ 500.00	
21 Hours	Rig Time @\$55.00 per hour	1155.00	
5	Shots @\$70.00 each	350.00	
4	Sacks Cement @\$7.25 each	29.00	
	Sand	10.00	
3	Rights Expense f/2 Men @\$35 ea. per night	210.00	
		<u>\$2254.00</u>	
	Sales Tax On \$2044.00	102.20	
		<u>\$2356.20</u>	
10-12-87	Moved rig in on location.		
10-13-87	Dug 3 cellars, checked hole, plugged off bottom with sand to 3736' and 4 sacks cement, rigged up.		
10-14-87	Shot and worked pipe @2200', 1800', 1400', 1000', 812', laid down 25 joints of 4-1/2" casing, core down.		
10-15-87	Plugged surface with 5 sacks balls and 200 sacks econolite. Plugging Complete.		

Commission Expires