

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20.901 ⁰⁰⁻⁰⁰

LEASE NAME Byrne ~~44-24~~ 41-24

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4620' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 24 TWP. 6S RGE. 30 (EXX) (W)

COUNTY Sheridan

Date Well Completed 7-24-87

Plugging Commenced 7-25-87

Plugging Completed 7-25-87

LEASE OPERATOR PanCanadian Petroleum, CO

ADDRESS Box 929 Denver Co. 80201

PHONE#(303) 825-8371 OPERATORS LICENSE NO. 8000

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dist #6, Hays Kansas: Gilbert Leiker

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	316	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump mud to 2580', set 1st plug from 2580' to 2480' w/25 sx; pump mud to 1760', set 2nd plug from 1760' to 1360' w/100 sx & 15 sx floccal; pump mud to 340' set 3rd plug from 340' to 180' w/40 sx cement; pump mud to 40' set 4th plug with wiper plug @ 40' & cement from 40' to surface. Pump 15 sx cement in rathole. All cement 60-40 posmix, 6% gel
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Bldg. Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 801 Union Center Bldg.

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 87

Carmen L. Adelson
Notary Public
Carmen L. Adelson

My Commission Expires: 8-21-90



7-30-87