

15-179-20121-0800

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County, Sec. 16 Twp. 6 Rge. 28 (E) (W) X

Location as "NE/CNW%SW%" or footage from lines SE SE NW  
Lease Owner Petroleum Management Inc.  
Lease Name Geisinger Well No. #1  
Office Address Box 922, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 1-19-70 19\_\_\_\_  
Plugging completed 1-21-70 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4210' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	4210'	1827.93'
				8 5/8"	338'	
RECEIVED STATE CORPORATION COMMISSION JAN 26 1970 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4000', mixed and ran 3 sacks cement thru dump bailer.  
Squeezed hole with 5 sacks hulls, followed with 5 sacks gel, followed with 100 sacks cement. Cement from 1650' to 1325' followed with 24 sacks gel. Gel from 1325' to 250' followed with 25 sacks cement. Cement from 350' to 275', followed with 6 sacks gel. Gel from 275' to 35' and displaced with 10 sacks cement. Cement from 35' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.


Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn to, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of January, 19 70.

My commission expires 1972

Sidney D. Miller  
Notary Public.



13-179-20121-00-00

I believe there is an error in the description of this well as shown on the Plugging Authority dated 12/15/69.

The well located NW-NW-SE, 16-6-28, Sheridan County was plugged 7/26/69 and a Plugging Authority was issued on it dated 7/29/69 however the "Authority" lists the well as Geisinger #1 and according to my records I reported it as Geisinger #B-1 as shown on the Intent to Drill Sheet dated 7/17/69.

The well reported here is located SE-SE-NW, 16-6-28, Sheridan County and is listed on the Intent to Drill Sheet dated 8/2/68 and shows as Geisinger #1, 2200' FNL & 2200' FWL, 16-6-28, Sheridan County as I have reported it.

There was a well drilled on this same quarter listed on the Intent to Drill Sheet dated 5/27/69 which I plugged 6/2/69 with Plugging Authority dated 6/5/69.

  
W. L. Nichols

15-179-20121-0-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1970  
CONSERVATION DIVISION  
WICHITA, KANSAS

DRILLERS LOG

No. 1 Geisinger

CASING RECORD:                      COMPANY:                      Petroleum Management, Inc.                      DESCRIPTION:  
 8 5/8" @ 328'                      CONTRACTOR:                      Red Tiger Drilling Co.                      2200' fml &  
 w/250 ex cement                      COMMENCED:                      August 3, 1968                      2200' fml of  
 4 1/2" @ 4208'                      COMPLETED:                      August 10, 1968                      Sec. 16-68-28W  
 w/250 ex cement                                                                                     Sheridan Co., Ks.  
 TOTAL DEPTH:                      4210'                      ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	60	
Sand & Shale	60	355	
Shale	355	1170	
Shale & Sand Strd.	1170	2035	
Shale	2035	2131	
Blaine Anhydrite	2131	2136	
Shale & Sand	2136	2528	
Anhydrite	2528	2564	
Shale	2564	2770	
Shale & Lime Shells	2770	3085	
Shale & Lime	3085	3805	
Lime	3805	4115	
Lime & Shale	4115	4150	
Lime	4150	4210	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

*Norman E. Klein*  
 Norman E. Klein

Subscribed and sworn to before me this 14th day of August, 1968.

*Butler M. Maloney*  
 Notary Public

My Commission Expires:  
3-22-71