

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD JUL 28 2005
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Hartman Oil Co., Inc.

Address: 12950 E 13th St. N - Wichita, Ks. 67230-1457

Phone: (620) 277-2511 Operator License #: 30535

Type of Well: P & A - Oil KCC 7-28-05 BEM RSDMS Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7/21/05 (Date)

by: Steve Durant W/ KCC - Witness by Ken Jehlik (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
St. Louis Depth to Top: 4714' Bottom: 4722' T.D. 4842'
Morrow Depth to Top: 4632' Bottom: 4638' T.D. 4842'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 055-20045-00-00

Lease Name: Finnup E

Well Number: #2

Spot Location (QQQQ): _____ - C - NW - NE

660 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 8 Twp. 22 S. R. 33 East West

County: Finney

Date Well Completed: 10-9-71

Plugging Commenced: 7-19-05

Plugging Completed: 7-21-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		424'	surface	10-3/4"	424'	none
		4842'	SURFACE	7"	4842'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

set CIBP @ 4308' - 1st plug @ 4300' -W/ 25 sks - 2nd plug @ 2000' W/40 sks - 3rd plug @ 1200' W/40 sks - 4th plug @ 480' W/40 SKS
5th plug @ 40' W/30 sks - Pumped 10 sks down backside between 10-3/4' & 7' CSG @ 200# - 7-19-05
7-21-05 - Re-filled 7" CSG from 525' to surface w/ 90 sks - 60-40 w/ 6 % Gel cement

Name of Plugging Contractor: Allied cement Co. & Hartman Oil Co., Inc. License #: 30535 99996

Address: 12950 E 13th St N - Wichita , Ks. 67230-1457

Name of Party Responsible for Plugging Fees: Hartman Oil Co., Inc.

State of Kansas County, Finney, ss.

S T Mitchell (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) S.T. Mitchell

(Address) 4550 W 9 Mi Rd Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 26th day of July, 20 05

Meryl L. King My Commission Expires: 2/7/2006
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, KS 67202

