

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Dart Cherokee Basin Operating Co. LLC  
 Address: 3541 County Road 5400, Independence, Ks. 67301  
 Phone: (620) 331-7870 Operator License #: 33074  
 Type of Well: SWD Docket #: D-24260  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: July 11, 2005 (Date)  
 by: Alan Dunning (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
Arbuckle Depth to Top: 1394 Bottom: 1422 T.D. 1430  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

25997-00-00

API Number: 15-125-90793-00-00  
 Lease Name: Scott  
 Well Number: 10  
 Spot Location (QQQQ): SW - NE - NE - NW *KCC BEM 7-20-05*  
4780 Feet from  North /  South Section Line *RBBMS Per Footages*  
3140 Feet from  East /  West Section Line  
 Sec. 10 Twp. 31 S. R. 15E  East  West  
 County: Montgomery  
 Date Well Completed: N/A  
 Plugging Commenced: 7/11/05  
 Plugging Completed: 7/12/05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	20'	10"		
		0	1430'	2 7/8"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1 inch pipe inside casing to 1300 feet. Pumped 210 sacks of portland cement in well with no return.  
Pulled out 1 inch pipe and let well set overnight. Ran 1 inch to cement at 750 feet. Filled well from 750 feet to surface. Pulled out 1 inch and topped off well. Cut off casing and restored location.  
A total of 238 sacks of portland cement were used to plug this well.

Name of Plugging Contractor: Kepley Well Service. License #: 30670  
 Address: 19245 Ford Road, Chanute, Ks. 66720

Name of Party Responsible for Plugging Fees: Dart Cherokee Basin Operating Co. LLC.  
 State of Kansas County, Montgomery, ss.

Tony Williams (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Tony Williams  
 (Address) 3541 County Road 5400, Independence, Ks. 67301

SUBSCRIBED and SWORN TO before me this 18th day of July, 20 05  
Lisa Shartzner My Commission Expires: 5-26-06  
 Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
 JUL 20 2005  
 KCC WICHITA  
*Bm*