

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-083-21503-00-00
LEASE NAME Snodgrass 'A'
WELL NUMBER No. 1-8

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

660 Ft. from South Line of Section
1650 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION E/2 SW SE
ADDRESS 8080 E. Central, Ste 300 Section 8 Township 23s Range 24w
CITY, STATE, ZIP Wichita, Kansas 67206 County Hodgeman
PHONE # 316-636-2737 Date Well Completed 08/05/05
Character of Well Dry and Abandoned Date Plugging Commenced 08/05/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 08/06/05
The plugging proposal was approved on August 5, 2005 (date)
by Greg Patterson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4800
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil, Sands and Clay		0	180	8-5/8"	211'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugging orders received from Greg Patterson at 4:15pm on 08/5/05. Plugged using 185 sx of; 60/40 Poz, 6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx at 1650', 2nd plug 50 sx at 860', 3rd plug 50 sx at 240', top plug 10 sx at 40' cemented to surface. Plugged rathole with 15 sx, mousehole with 10 sx. Plugging completed at 12:30 am on 08/06/05 by Allied Cementing. Ticket # 17961.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 8th day of August, 2005

Pamela S. Fields
(Notary Public)



My Commission Expires:

RECEIVED
AUG 09 2005
KCC WICHITA

Form CP-4
Revised 12-92

AUG 09 2005
KCC WICHITA

Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Snodgrass 'A' No. 1-8

LOCATION: E/2 SW SE
API: 15-083-21503-00-00

Section 8 T 23s R 24w
Hodgeman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #2

COMMENCED: 07/25/05
COMPLETED: 08/06/05

TOTAL DEPTH:	DRILLER	4800	FEET
	LOGGER	4796	FEET

Ground Elevation: 2428
KB Elevation: 2439

LOG

0 -	2 FEET	Top Soil
2 -	170 FEET	Surface Sands and Clay
170 -	1637 FEET	Clays, Sandstone and Shales
1637 -	1673 FEET	Anhydrite (Driller's)
1673 -	2560 FEET	Shales and Salt
2560 -	4800 FEET	Limestone/Shales

CASING RECORDS

Spud at 8:15 pm on 07/25/05. Drilled 12-1/4" hole to 227'. Ran 5 joints of new 23# 8-5/8" casing, tally 211' set at 227' KB. Welded collars all joints. Strapped bottom 3 joints. Cemented with 150 sx Common; 3% CC; 2% Gel. Cement did circulate. Plug down at 5:00 am on 07/26/05. Allied Cementing ticket # 17239.

PLUGGING RECORD

Plugging orders received from Greg Patterson at 4:15pm on 08/5/05. Plugged using 185 sx of; 60/40 Poz, 6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx at 1650', 2nd plug 50 sx at 860', 3rd plug 50 sx at 240', top plug 10 sx at 40' cemented to surface. Plugged rathole with 15 sx, mousehole with 10 sx. Plugging completed at 12:30 am on 08/06/05 by Allied Cementing. Ticket # 17961. SDC notified KCC on 08/08/05 of plugging.

DEVIATION SURVEYS

3/4 degree(s) at	227	feet
3/4 degree(s) at	2686	feet
3/4 degree(s) at	3753	feet
3/4 degree(s) at	4800	feet

RECEIVED
AUG 09 2005
KCC WICHITA