

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

AUG 10 2005

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

077-00974-00-00

Lease Operator: R & B Oil & Gas, Inc.
Address: 111 N. Blaine, Attica, KS 67009
Phone: (620) 257-7251 Operator License #: 31191
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-30-05 (Date)
by: David P Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Simpson Depth to Top: 4714 Bottom: 4720 T.D. 4762

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - Spud 1-1-59
Lease Name: Muir
Well Number: 2
Spot Location (QQQQ): C - W2 - W2 - SE4
1320 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 9 Twp. 32 S. R. 7 East West
County: Harper
Date Well Completed: Spudded 1-1-59
Plugging Commenced: 7-11-05
Plugging Completed: 7-12-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Simpson</u>	<u>Oil</u>	<u>4714</u>	<u>4720</u>	<u>8 5/8</u>	<u>218</u>	
				<u>5 1/2</u>	<u>4761</u>	<u>1510</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4655', dumped 5 sacks cement; ripped 1510', pulled to 1300', pumped 35 sacks; pulled to 700', pumped 35 sacks; pulled to 270', circulated with 110 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
State of Kansas County, Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Newberry
(Address) PO Box 195 Attica, KS 67009

REBECCA S. NEWBERRY
Notary Public - State of Kansas
My Appt. Expires 1-21-09

SUBSCRIBED and SWORN TO before me this 8th day of August, 2005
Rebecca S. Newberry Notary Public My Commission Expires: 7-21-2009

ALLIED CEMENTING CO., INC. 16202

Federal Tax I.D.# ~~000000~~

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
M.L.

DATE <u>7-12-05</u>	SEC. <u>9</u>	TWP. <u>32s</u>	RANGE <u>7w</u>	CALLED OUT <u>9:00 AM</u>	ON LOCATION <u>9:45 AM</u>	JOB START <u>10:20 AM</u>	JOB FINISH <u>11:45 AM</u>
LEASE <u>moie</u>	WELL # <u># 2</u>	LOCATION <u>160 & 14th 2 north,</u>			COUNTY <u>Harper</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD <input type="radio"/> OR NEW (Circle one)		LOCATION <u>2 1/2 west Cross 1st Bridge north into</u>					

RECEIVED
AUG 10 2005
KCC WICHITA

CONTRACTOR Quality Well Service OWNER R+B Oil & Gas

TYPE OF JOB ohp
HOLE SIZE 7 7/8" T.D. 1300' CEMENT AMOUNT ORDERED 180sx 60:40:4

CASING SIZE 5 1/2" DEPTH 1300
TUBING SIZE DEPTH
DRILL PIPE DEPTH

TOOL DEPTH
PRES. MAX 300 MINIMUM 50
MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.
PERFS.
DISPLACEMENT fresh h₂O

EQUIPMENT

PUMP TRUCK CEMENTER Mike Rucker
302 HELPER Tracy Cushman
BULK TRUCK
389 DRIVER Mike Becker
BULK TRUCK
DRIVER Brad Martin

COMMON	<u>108 A</u>	@	<u>8.70</u>	<u>939.60</u>
POZMIX	<u>72</u>	@	<u>4.70</u>	<u>338.40</u>
GEL	<u>6</u>	@	<u>14.00</u>	<u>84.00</u>
CHLORIDE		@		
ASC		@		
HANDLING	<u>186</u>	@	<u>1.60</u>	<u>297.60</u>
MILEAGE	<u>35 X 186 X .06</u>			<u>390.60</u>
TOTAL				<u>2050.20</u>

REMARKS:

1st Plug 1300' - 10:20 AM load hole with fresh mix 35sx 60:40:4 @ 14.0 weight. Displace with fresh h₂O.
2nd Plug 700' - 10:55 AM load hole with fresh mix 35sx 60:40:4 @ 14.0 weight. Displace with fresh h₂O.
3rd Plug: 11:25 AM 270' Circ. to Surface. Mix 110sx 60:40:4 @ 14.0 weight Disp. with fresh h₂O

SERVICE

DEPTH OF JOB	<u>1300'</u>			
PUMP TRUCK CHARGE				<u>600.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>35</u>	@	<u>5.00</u>	<u>175.00</u>
TOTAL				<u>775.00</u>

CHARGE TO: R+B Oil & Gas
STREET _____
CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

MANIFOLD	<u>NONE</u>	@		
		@		
		@		
		@		
		@		

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING

TAX _____
TOTAL CHARGE ~~_____~~
DISCOUNT ~~_____~~ IF PAID IN 30 DAYS

SIGNATURE [Signature] PRINTED NAME _____