

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-00204-0000

LEASE NAME MCCLAREN

WELL NUMBER 1-6

2540' FSL Ft. from S Section Line

2540' FWL Ft. from E Section Line

SEC. 6 TWP. 30S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 4/14/46

Plugging Commenced 8/05/05

Plugging Completed 8/05/05

RECEIVED
AUG 15 2005
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 3075' GL Bottom 2738' T.D. 2763'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2479'	2709'	10 3/4"	656'	0
				7"	2744'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

8/5/05 P&A Op not witnessed. Set CIBP @2420' KB, spot 20' cmt. Revise PBTD @2400'. TOC@surface.NU cmtr. load hole w/29ppg 36cp mud & 25 sx cmt 1700'-1575'. Pmp 36 bbl mud 675' & 50 sx cmt plug 675'-525' & 19 bbl mud to 50'. Pump 10 sx cmt 50'-0'. Cut 7" csg & 10 3/4" csg 3' bgl. weld on trash cover - ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.


LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 11TH day of August, 20 05

My Commission Expires: 3/23/06



USE ONLY ONE SIDE OF EACH FORM

Form CP-4
Revised 05-88

[Handwritten mark]