

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
AUG 12 2005
Type or Print on this Form
Form must be Signed
All blanks must be Filled
KCC WICHITA

Form CP-4

December 2003

Lease Operator: R & B Oil & Gas, Inc.
Address: 111 N. Blaine, Attica, KS 67009
Phone: (620) 254-7251 Operator License #: 31191
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: June 16, 2005 (Date)
by: David P Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 4223 Bottom: 4290 T.D. 4313

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-095-10039-00-00
Lease Name: Graber
Well Number: B-2
Spot Location (QQQQ): _____ - NE - NW - NE
330 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 13 Twp. 30 S. R. 9 East West
County: Kingman
Date Well Completed: _____
Plugging Commenced: 06-17-05
Plugging Completed: 06-21-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Miss	Gas	4223	4290	8 5/8	251	
				4 1/2	4310	2600'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole, sand was at 4170', dumped 4 sacks cement, had 22" stretch. Ripped casing at 2820', 2600', casing came free.
Pulled to 1250', pumped 35 sacks, pulled to 750', pumped 35 sacks, pulled to 300', circulated with 120 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554
Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
State of Kansas County, Harper, ss.

Randy Newberry (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Randy Newberry
904 N Logan Attica, KS 67009
(Address)



SUBSCRIBED and SWORN TO before me this 11th day of August, 2005
Rebecca S. Newberry My Commission Expires: 7-21-2009
Notary Public

United Cementing and Acid Co., Inc.

SERVICE TICKET

6746

6272 ✓

Oil Well Cementing & Acidizing
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720
 2510 West 6th Street • El Dorado, KS 67042

DATE 6-21-05

COUNTY Kingman CITY _____

CHARGE TO R+B

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. Comber # B-2 CONTRACTOR Quality Well Serv.

KIND OF JOB Old Hole Plug SEC. 13 TWP. 30 S RNG. 9 West

DIR. TO LOC 4 1/2 West of Spivey South Intn. OLD NEW

Quantity	MATERIAL USED	Serv. Charge
18256	60/400007 4% gel @4.90	500.00
854	gel @9.79	891.80
		77.60
RECEIVED		
AUG 12 2005		
KCC WICHITA		
19054	BULK CHARGE	1810.20
30	BULK TRK. MILES <u>9.50 tons</u>	218.05
30	PUMP TRK. MILES	121.90
	PLUGS	
	<u>DESD</u> SALES TAX	102.03
	TOTAL	5077.18

T.D. 4313ft.

CSG. SET AT _____ VOLUME _____

SIZE HOLE _____

TBG SET AT _____ VOLUME _____

MAX. PRESS. _____

SIZE PIPE 4 1/2" casing

PLUG DEPTH _____

PKER DEPTH _____

PLUG USED _____

TIME ON LOCATION 12:00 TIME FINISHED _____

REMARKS: Pulled 4 1/2" casing up to 125ft. Brake circulation. Mix pump 355X60K000 4% gel + displacement to 125ft. Pulled up to 750ft. Brake circulation. Mix pump 355X60K000 4% gel + displacement to 750ft. Pulled up to 300ft. Brake circulation. Mix pump. 1125X60K000 4% gel to surface. Cement stayed in the cellar.

EQUIPMENT USED

NAME Shawn Scobber P-14 UNIT NO. _____

NAME Steve Davis B-1 UNIT NO. _____

James K. ...
 CEMENTER OR TREATER

OWNER'S REP.