

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: James D. Lorenz
Address: 543A 22000 Road, Cherryvale, Kansas 67335-8515
Phone: (620) 328-4433 Operator License #: 9313
Type of Well: Gas Docket #: N/a
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-09-04 (Date)
by: John Almond (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☒ Yes ☐ No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 280 Bottom: 288 T.D. 288
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number: 15 - 205-2544/2-00-00
Lease Name: Eisele
Well Number: #8
Spot Location (QQQQ): SW - SE - NW 8-16-05
3630 Feet from ☐ North / ☒ South Section Line for Footages
4950 Feet from ☒ East / ☐ West Section Line
Sec. 35 Twp. 29 S. R. 15 ☒ East ☐ West
County: Wilson
Date Well Completed: 10-10-01
Plugging Commenced: 12-09-04
Plugging Completed: 12-09-04


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		20'	0	7"		cemented to surface
		288'	0	27/8"		cemented to surface

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked onto the 27/8" casing, circulated with 10 Bls. of water then blended & pumped 20 sx. of Portland cement, closed well in at 250 psi.

Name of Plugging Contractor: L & S Well Service, L.L.C.
Address: 543A 22000 Road Cherryvale, Kansas 67335-8515
Name of Party Responsible for Plugging Fees: James D. Lorenz
State of Kansas County, Labette, ss.
Helen L. Lorenz (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) _____
(Address) 543A 22000 Road Cherryvale, Kansas 67335-8515
SUBSCRIBED and SWORN TO before me this 12th day of December, 20 04
Lisa J. Lorenz My Commission Expires: 2-19-2008
Notary Public

James D. Lorenz KCC Lic. #9313
543A 22000 ROAD
CHERRYVALE, KANSAS 67335-8515
620-328-4433 OFFICE

TICKET NUMBER _____
LOCATION _____
FOREMAN _____

AP-15-205-25442-0000 CEMENT TREATMENT REPORT

DATE 12-09-00	CUSTOMER#	WELL NAME EISELE	8
SECTION 35	TOWNSHIP 29	RANGE 15	COUNTY WILLSON
CUSTOMER JIM LORENZ			
MAILING ADDRESS 543A 22000 Road			
CITY Cherryvale			
STATE Kansas		ZIP CODE 67335	
TIME ARRIVED ON LOCATION			

HOLE	PIPE	ANNUAL VOLUME IN LINEAR FT./BL.
6 3/4"	4 1/2"	40.5
6 1/4"	4 1/2"	54.5
6 1/4"	2 1/2"	33.5
5 1/4"	2 1/2"	53.5
5 1/4"	2"	47
TUBING-LINEAR FT./BL.		
4 1/2"	9.5 lb.	61.7
4 1/2"	10.5 lb.	63.1
4 1/2"	11.6 lb.	64.5
2 1/2"		170
2"		250

WELL DATA	
HOLE SIZE 6 1/4	
TOTAL DEPTH 288	
CASING SIZE 2 1/2	
CASING DEPTH 288	
OPEN HOLE	
PACKER DEPTH 280	
WIRE LINE	READING BEFORE
WIRE LINE	READING AFTER
TREATMENT VIA	

TYPE OF TREATMENT

- () SURFACE PIPE
() PRODUCTION CASING
() SQUEEZE CEMENT
☒ PLUG AND ABANDON ALT-NO2 WELL
() PLUG BACK
() MISP. PUMP
() WASH DOWN
() OTHER

RECEIVED

AUG 15 2005

KCC WICHITA

INSTRUCTIONS PRIOR TO JOB

AUTHORIZATION TO PROCEED

TITLE

DATE

HOOKED ONTO 2 7/8 "CASING. ESTABLISHED CIRCULATION WITH 0 BARRELS OF WATER, RAN
3x GEL, 3x COTTONSEED HULLS, 8x ME 5x METASILICATE HEAD, THEN BLENDED AND PUMPED
30 SACKS OF PORTLAND CEMENT, THEN DROPPED RUBBER PLUG, THEN PUMPED
BARRELS OF WATER.

- () PLUG ON BOTTOM
☒ SHUT IN PRESSURE 250
() LOST CIRCULATION
() GOOD CEMENT RETURNS
() TOPPED OFF WELL WITH _____ SACKS

(SIGNATURE)