

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

AUG 15 2005

KCC WICHITA

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior Inc. Address: P.O. Box 399 Garden City Ks. 67846 Phone: (620) 272-1023 Operator License #: 4058 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 8/9/05 (Date) by: Ken (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (if needed attach another sheet) Marmaton Depth to Top: 4456' Bottom: 4475' T.D. Cherokee Depth to Top: 4518' Bottom: 4528' T.D. 4540'

API Number: 15-101-21442-00-00 Lease Name: Eaton Well Number: 1-15 Spot Location (QQQQ): C SW - NE - NE - NE 4786' Feet from [] North / [X] South Section Line 494' Feet from [X] East / [] West Section Line Sec. 15 Twp. 17 S. R. 29 [] East [X] West County: Lane Date Well Completed: 1/4/88 Plugging Commenced: 8/9/05 Plugging Completed: 8/9/05

KCC DENIED 8-11-05 RBW/m

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows for Marmaton and Cherokee formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4410'w/ 2sx cement. Ran 71 jts 27/8 tbg to 2200'. Swift hooked up to 27/8 tbg and pumped 30sx 60/40 pos cement. Pulled 71 jts 27/8 tbg. Perf 1250' to 1251',4spf. Swift hooked up to 51/2 casing and pumped 175sx 60/40 pos w/ 200# hulls. Swift hooked up to 51/2 annulus and pressured to 500# held.

Name of Plugging Contractor: Swift Services License #: 32382 Address: P.O. Box 466 Ness City Ks. 67560

Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Ks. County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 12 day of August, 2005

[Signature of Debra J. Purcell]

My Commission Expires: 11/4/07

DEBRA J. PURCELL Notary Public - State of Kansas My Appt. Expires 11/4/07

KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]