

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-00209-0000

LEASE NAME KOENIG

WELL NUMBER 2-11

2507
2540' FSL Ft. from S Section Line

2886
2740' FEL Ft. from E Section Line

KCC
BEM
8-16-05
GPS per DIST

SEC. 11 TWP. 30S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 06/25/45

Plugging Commenced 8/01/05

Plugging Completed 8/03/05

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 072) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CHASE Depth to Top 2723' KB Bottom 2730' T.D. 2730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2684'	2470'	10 3/4"	579'	0
				7"	2525'	1027'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

8/1-8/3/05 P&A Op witnessed by J. Holland, KCC. Unable to set CIBP, NU cmtr to 7" csg, Pmp 500# csh w/ 15 bbl mud & 40 sx cmt. Tag TOC @2035', load csg w/13 bbl mud. Pmp 40sx cmt 1700'-1500'. Pmp 50 bbl mud to 200'. Cut csg @1027'. Circ w/ 40 ppg mud, Pmp 75 sx cmt 600'-450', disp w/17 bbl mud, load csg w/5 ppg mud to 40', pmp 20 sx cmt plug 40'-0', cut 10 3/4" surf csg 3' bgl, weld on trash cover-ID plate


Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 10TH day of August, 20 05

Deborah Pollock
My Commission Expires: 4/2/09 Notary Public