

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

AUG 16 2005

Form GP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Hirschmann, Curtis

Lease Operator: Curt's Oil Operations

Address: P.O. Box 8, Great Bend, Ks. 67530

Phone: (620) 653-7330 Operator License #: 4871

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: August 8th, 2005 (Date)

by: Bruce Basye (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: <u>3080'</u>	Bottom: <u>AP.3333'</u>	T.D. <u>3340'</u>
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15 - ~~NA~~ 009 - 30227-00-00

Lease Name: Ringering

Well Number: #6

Spot Location (QQQQ): E/2 - SE - SW - NW

330' Feet from North / South Section Line

1650' Feet from East / West Section Line

Sec. 15 Twp. 20 S. R. 11 East West

County: Barton 10/14/1965

Date Well Completed: 02/16/1964

Plugging Commenced: August 10th, 2005

Plugging Completed: August 10th, 2005

KCC
BEM
8-11-05
RBDMS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	225'	8-5/8"	225'	0'
	Production	0'	3336'	5-1/2"	3336'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Ran in 65 joints to 2000' - cemented and pulled 20 joints to 1400' - cemented and pulled 28 joints to 520' - cemented to top.

Pulled rest of tubing. Rigged down and moved off. Cement info: Mix 140 sacks - 60/40 poz - 10% gel with 250# hulls - 2100' - good circulation;

Mix 150 sacks - 60/40 poz - 10% gel with 250# hulls - 1325'; Circulated to surface, pulled tubing out of hole and top off with 75 sacks.

Circulated out Braden head. 365 sacks cement.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901


Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Curt's Oil Operations

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 11th day of August, 20 05

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bem