

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD AUG 16 2005
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Hitchmann, Curtis

KCC WICHITA

Lease Operator: ^{DBH} Curt's Oil Operations
Address: P.O. Box 8, Great Bend, Ks. 67530
Phone: (620) 653-7330 Operator License #: 4871
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August 8th, 2005 (Date)
by: Bruce Basye (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 3305' Bottom: 3312' T.D. 3339'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - N/A 009-23325-00-01
Lease Name: Ringering
Well Number: #1
Spot Location (QQQQ): _____ - C - SE - NW
3300' Feet from North / South Section Line
~~2310~~ 3300 Feet from East / West Section Line
Sec. 15 Twp. 20 S. R. 11 East West
County: Barton
Date Well Completed: 02/16/1964
Plugging Commenced: August 10th, 2005
Plugging Completed: August 10th, 2005

KCC
BEM
8.16.05
RBDMS
CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	222'	8-5/8"	222'	0'
	Production	0'	3338'	5-1/2"	3338'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Ran in 3-7/8" bit. Had to drill some at 18 & 20 joints and again at 35 joints. Ran on down to 2100'. Pulled back out. Rigged up perforators - shot 3 guns: 1325', 515' and 275'. Ran tubing back in to 2100'. Cemented and pulled 26 joints - cemented to top. Pulled rest of tubing, rigged down and moved off.
Cement Info: 2065' - 140 sacks - 60/40 poz - 10% gel with 200# hulls; 1400' - 110 sacks - 60/40 poz - 10% gel with 250# hulls - Lost circulation; 550' - 60 sacks - 60/40 poz - 10% gel with 100# hulls - circulated to surface. Top off 25 sacks down casing - Braden head - 10 sks - 200#. 345 sacks cement.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525
Name of Party Responsible for Plugging Fees: Curt's Oil Operations
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 11th day of August, 2005
(Signature) Karen J. Mitchell My Commission Expires: 4/13/06
Notary Public

Bm