

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1
Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

RECEIVED
AUG 09 2005
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-083-21503-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation
(owner/company name)

KCC LICENSE # 5003
(operator's) *6/06*

ADDRESS: 8080 E. Central, Ste 300 CITY: Wichita
STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737

LEASE: Snodgrass 'A' WELL#: No. 1-8 Section 8 Township 23s Range 24w
E/2 SW SE SPOT LOCATION/QQQQ COUNTY: Hodgeman
660 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
1650 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8-5/8" SET AT 227' KB CEMENTED WITH 150 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2428 G.L. 2439 K.B. T.D. 4800 PBDT _____ Anhydrite Depth 1637
(Stone Corral Formation)
CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugging orders received from Greg Patterson at 4:15pm on 08/5/05. Plugged using 185 sx of; 60/40 Poz,
6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx at 1650', 2nd plug
50 sx at 860', 3rd plug 50 sx at 240', top plug 10 sx at 40' cemented to surface. Plugged rathole with 15 sx,
mousehole with 10 sx. Plugging completed at 12:30 am on 08/06/05 by Allied Cementing. Ticket # 17961.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Bill Craig/Gary M. Talbott Phone#: (316) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's) *6/06*
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 12:30 am on August 6, 2005. Plugged
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____
DATE: 08/06/05 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

RECEIVED
AUG 09 2005
KCC WICHITA

Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Snodgrass 'A' No. 1-8

LOCATION: E/2 SW SE
API: 15-083-21503-00-00

Section 8 T 23s R 24w
Hodgeman County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #2

COMMENCED: 07/25/05
COMPLETED: 08/06/05

TOTAL DEPTH:	DRILLER	4800	FEET
	LOGGER	4796	FEET

Ground Elevation: 2428
KB Elevation: 2439

LOG

0 -	2 FEET	Top Soil
2 -	170 FEET	Surface Sands and Clay
170 -	1637 FEET	Clays, Sandstone and Shales
1637 -	1673 FEET	Anhydrite (Driller's)
1673 -	2560 FEET	Shales and Salt
2560 -	4800 FEET	Limestone/Shales

CASING RECORDS

Spud at 8:15 pm on 07/25/05. Drilled 12-1/4" hole to 227'. Ran 5 joints of new 23# 8-5/8" casing, tally 211' set at 227' KB. Welded collars all joints. Strapped bottom 3 joints. Cemented with 150 sx Common; 3% CC; 2% Gel. Cement did circulate. Plug down at 5:00 am on 07/26/05. Allied Cementing ticket # 17239.

PLUGGING RECORD

Plugging orders received from Greg Patterson at 4:15pm on 08/5/05. Plugged using 185 sx of; 60/40 Poz, 6% Gel and 1/4#/sx Flow Seal as follows: Heavy mud in hole, Bottom plug 50 sx at 1650', 2nd plug 50 sx at 860', 3rd plug 50 sx at 240', top plug 10 sx at 40' cemented to surface. Plugged rathole with 15 sx, mousehole with 10 sx. Plugging completed at 12:30 am on 08/06/05 by Allied Cementing. Ticket # 17961. SDC notified KCC on 08/08/05 of plugging.

DEVIATION SURVEYS

3/4 degree(s) at	227	feet
3/4 degree(s) at	2686	feet
3/4 degree(s) at	3753	feet
3/4 degree(s) at	4800	feet

RECEIVED
AUG 09 2005
KCC WICHITA