

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-179-00024-00-00

WELL PLUGGING APPLICATION FORM

File One Copy

Inc.

Lease Owner Anschutz Drilling Address 709 Union Nat'l Bk Bldg.
(Applicant) Wichita, Ks.

Lease (Farm Name) Wyant well No. 1

Well Location C/North line NE/4 Sec. 25 Twp. 6 Rge. 30 (E)-(W)

County Sheridan Field Name (if any) _____

Total Depth 4585' Oil Gas Dry Hole X

Was well log filed with application? Yes. If not, explain: _____

Date and hour plugging is desired to begin 9-6-52

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

G. I. Schmidt Address Hays, Kansas

Name of Plugging Contractor Anschutz Drilling Co., Inc.

Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to Anschutz Drilling Co., Inc. Address 709 Union Nat'l Bk Bldg., Wichita, Ks.
and payment will be guaranteed by applicant.

STATE CORPORATION COMMISSION

SEP 24 1952

Leon G. Mehlis
Applicant or Acting Agent

CONSERVATION DIVISION Date September 8, 1952
Wichita, Kansas

9-24-52

PLUGGING
FILE SEC 25 T 6 R 30
BOOK 43 PAGE 2

15-179-00024-00-00

DRILLER'S LOG

Anschutz Drilling Company, Inc.
#1 Wyant
C NL NE $\frac{1}{4}$ Sec. 25-6S-30W
Sheridan Co., Kansas

<u>FROM</u>	<u>TO</u>	
0	230	Sand
230	675	Shale
675	1000	Shale & Sand Streaks
1000	1460	Shale, Shells & Sand
1460	1560	Sand
1560	1695	Shale, Sand & Shells
1695	1840	Sand
1840	1960	Sand & Shale
1960	1990	Shale & Shells
1990	2040	Sand
2040	2150	Shale & Shells
2150	2175	Anhydrite
2175	2265	Shale, Shell Red Bed
2265	2595	Red Bed Shale
2595	2635	Anhydrite
2635	2800	Shale & Shells
2800	2900	Shale, Shell & Lime
2900	3030	Shale & Shells
3030	3175	Shale & Lime
3175	3335	Shale
3335	3450	Lime & Shale
3450	3523	Shale & Lime
3523	3703	Lime & Shale
3703	3929	Lime
3929	4049	Lime & Shale
4049	4121	Lime
4121	4161	Lime & Chert
4161	4464	Lime & Shale
4464	4551	Lime, Shale & Chert
4551	4570	Cherty Conglomerate
4570	4585	Chert & Shale
	4585	TOTAL DEPTH

COMMENCED: 8-19-52

COMPLETED: 9-6-52

CASING RECORD

Set 8-5/8" surface casing at 252 feet with 200 sacks cement.

ELEVATION: 2896 RB

TOPS

Anhydrite 2595
Howard 3651
Topeka 3719
Heebner 3953
Lansing 3996
Base Kansas City 4219
Cherty Conglomerate 4509
Mississippi Limestone 4566
Mississippi Dolomite 4572

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the foregoing is a true and correct copy of the log of Anschutz Drilling Company, Inc., #1 Wyant, located C NL NE $\frac{1}{4}$ of Section 25-6S-30W, Sheridan County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *Leon L. Mehler*
Leon L. Mehler

Subscribed and sworn to before me this 16th day of September, 1952.

Arqueline L. ...
Notary Public
RECEIVED
STATE CORPORATION COMMISSION

My commission expires: May 2, 1956.

SEP 24 1952

CONSERVATION DIVISION
Topeka, Kansas

9-24-52

PLUGGING
FILE SEC 25 T 6 R 30W
BOOK PAGE 48 LINE 110



STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 800 BITTING BUILDING
 WICHITA, KANSAS

15-179-00024-00-00

September 8, 1952

Well No.	1
Lease	lyant
Description	Oil & Gas 25-6-30N
County	Sheridan
File No.	13-7

Anschutz Drilling Company
 709 Union Nat'l. Bank Bldg.
 Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION

BY: J. P. Roberts
 J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR