

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
AUG 25 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: LARSON OPERATING COMPANY
A DIVISION OF LARSON ENGINEERING, INC.

Address: 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

Phone: (620) 653-7368 Operator License #: 3842

Type of Well: OIL Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 8-8-05 (Date)

by: Ed Schumacher/Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Arbuckle Depth to Top: 3853' Bottom: 3872' T.D. _____

L-KC "K" Depth to Top: 3737' Bottom: 3740' T.D. _____

Topeka Depth to Top: 3408' Bottom: 3411' T.D. _____

API Number: 15-195-22008 - 00 - 00

Lease Name: DIETRICH

Well Number: 1

Spot Location (QQQQ): 50' W - NE - NE - SE

2310 Feet from North / South Section Line

380 Feet from East / West Section Line

Sec. 36 Twp. 11 S. R. 21 East West

County: TREGO

Date Well Completed: 4/22/1989

Plugging Commenced: 8/11/2005

Plugging Completed: 8/11/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	0'	218'	8-5/8"	218'	0'
L-KC "K"	oil	0	3950'	5-1/2"	3950'	0'
Topeka	oil					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

Plugged down 5-1/2" csg w/ 50 sx w/ 300# hulls, followed w/ 9 sx gel, finished w/ 170 sx w/ 300# hulls. Pressured 5-1/2" csg to 500#, shut in w/ 400#. Pressured 5-1/2"x 8-5/8" annulus to 300# - held. Plugged w/ 220 sx 60-40 poz w/ 10% gel, 600# hulls and 9 sx gel. Plugging complete @ 10:00 am, 8-11-05. KCC representative on location - Roger Moses.

Name of Plugging Contractor: ALLIED CEMENTING CO., INC. License #: _____

Address: P. O. BOX 31 RUSSELL, KS 67665

Name of Party Responsible for Plugging Fees: LARSON OPERATING COMPANY, A DIVISION OF LARSON ENGINEERING, INC.

State of KANSAS County, BARTON, ss.

THOMAS LARSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Thomas Larson PRESIDENT

(Address) 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

DEBRA J. LUDWIG
Notary Public - State of Kansas
My Appt. Expires 5/5/2008

SUBSCRIBED and SWORN TO before me this 22ND day of AUGUST, 2005

Debra J. Ludwig My Commission Expires: 5/5/2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm