


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Sheeidan County. Sec. 22 Twp. 6 Rge. 29 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW-NW-NW
Lease Owner Weston Hydrocarbon Co
Lease Name NEFF Well No. A-1
Office Address 770 Jones Bldg., Corpus Christi, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed July 7 1957
Application for plugging approved July 11 1957
Plugging commenced August 13 1957
Plugging completed August 29 1957
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production April 31 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays Kansas
Producing formation Kansas City Depth to top 3975 Bottom _____ Total Depth of Well 413 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	263	8 5/8"	263	None
		0	413	5 1/2"	413	903'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug Back with 5 sacks Cement to 4073'
Pulled casing - Mudded Hole to 263'
Set 10' Rock Bridge, Mix and Dump 20
Sacks Cement, Mud to 35', set 10' Rock
Bridge, Mix and Pour 10 Sack Cement to
Base of Casing

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE Pipe Pulling Company
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Pawnee, ss.
J. L. Haines (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Haines
Larned Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1957
Clarence Smith

My commission expires Jan. 21st 1958

Notary Public.

9-27-57
CONSERVATION DIVISION
Wichita, Kansas
FILE - SEC 22 T. 6 R 290
BOOK PAGE 26 LINE 28

15-179-05226-00-00

DRILLER'S LOG

Company - Westpan Hydrocarbon Company

Location - NW NW NW Sec. 22-6S-29W, Sheridan County, Kansas.

Contractor - Bill Hay Drilling Co.

Elevation - 2789' (KB)

Well No. - Neff No. A-1

Casing - 8 5/8" @ 263' w/160 sacks.

Commenced - November 9, 1953

5 1/2" @ 4112' w/160 sacks.

Completed - November 21, 1953

FORMATION

DEPTH

Surface Sand & Clay	220
Blue Shale	263
Sandy Shale	490
Shale & Sand	1175
Shale & Sandy Streaks	1350
Sand & Shells	1450
Sand	1615
Sand & Shale	1865
Shale & Shells	2245
Sand	2320
Sand & Shale	2460
Shale & Shells	2510
Anhydrite	2555
Shale & Shells	3025
Lime & Shale	3095
Shale & Lime	3335
Lime & Shale	3660
Shale & Lime	3857
Lime & Shale	4000
Lime	4113 TD

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 27 1957
 CONSERVATION DIVISION
 Wichita, Kansas

9-27-57

PLUGGING
 FILE SEC 22 T 6 R 24W
 BOOK PAGE 26 LINE 38