


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-179-05236-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 27 Twp. 6 Rge. 29 (W) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NW
Lease Owner Westpan Hydrocarbon Co
Lease Name Elaie Wessel Well No. 5
Office Address 2500 Johnson Dr. Kansas City 3 Ks
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ 19____
Application for plugging filed Dec 10 19 56
Application for plugging approved Dec 13 19 56
Plugging commenced Dec 21 19 56
Plugging completed Dec 25 19 56
Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4150' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	253'	none
				5 1/2	4150'	3003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 4070'
Dumped 4 sacks cement with dump bailer
Mudded hole to 240'
Set 10' rock bridge
Dumped 20 sacks cement
Mudded hole to 35'
Set rock bridge
Dumped 10 sacks cement to top surface pipe

Name of Plugging Contractor E & L Casing Pulling Co (If additional description is necessary, use BACK of this sheet)
Address Great Bend, Ks.

STATE OF Kansas COUNTY OF Pawnee, ss.
William J Bunting (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W J Bunting
Pawnee Rock Kans. (Address)

SUBSCRIBED AND SWORN TO before me this 9 day of Feb, 19 57
Dr. H. A. H. H. H. Notary Public.

My commission expires 7-11-57

PLUGGING
FILE SEC 27 T. 6 R 29W
BOOK PAGE 125 LINE 31

STATE CORPORATION COMMISSION
FEB 11 1957
CONS. DIVISION
Wichita, Kansas