

15-179-00046-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Sheridan County. Sec. 27 Twp. 6 Rge. 29 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW-NW-NW
Lease Owner Westpan Hydrocarbon Company
Lease Name Elsie Wessel Well No. 1
Office Address 720 Jones Bldg., Corpus Christie, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 27 19 53
Application for plugging filed July 9 19 57
Application for plugging approved July 11 19 57
Plugging commenced July 23 19 57
Plugging completed August 3 19 57
Reason for abandonment of well or producing formation No Fluid

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production May 31 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Kansas City Depth to top 4002' Bottom 4153' Total Depth of Well 4720' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	295	8-5/8"	295'	None
		0	4145'	5 1/2"	4145'	1478'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand from 4020 1/2 to 3990
Mudded Hole to 285', set 10' rock bridge,
Mixed and ~~XXXXXX~~ dumped 20 sacks of
cement
Mudded hole to 35', set 10' rock bridge,
Mixed and poured 10 sacks of cement
to base of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Pawnee
J.L.Haines (Agent) ~~XXXXXXXXXXXXXXXXXXXX~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.L.Haines
Box 30 Lained Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of Aug, 1957

My commission expires 7-11-61

[Signature]
Notary Public.

PLUGGING
FILE SEC 27 T. 6 R. 29W
BOOK PAGE 26 LINE 30

8-16-57
COMMISSION DIVISION

15-179-00046-00-00

DRILLER'S LOG

Company: Westpan Hydrocarbon Co.

SW NW NW
Sec. 27, Twp. 6S, Rge. 29W

Farm: Wessell #1

Total Depth: 4715'

County: Sheridan, Kansas

Comm: 12-4-52 Comp: 12-22-52

Contractor: Glenn W. Peel

Elevation:

Casing:

5 5/8" 289' con.
5 1/2" 4145' con.

Production:

Figures below indicate bottom of formations:

Top Soil & Sand	0 -	160
Sand & Shale		220
Shale		750
Sand & Shale		975
Shale & Shells		1910
Sand		1970
Shale & Shells		2070
Anhydrite		2095
Shale & Lime		2105
Shale & Sand		2160
Red Bed & Shale		2510
Shale & Lime		2535
Anhydrite		2577
Shale & Shells		2635
Red Bed & Shells		2685
Shale & Shells		2780
Shale & Lime		2910
Shale & Shells		3270
Lime		3345
Shale & Lime		3510
Lime		4155
Lime & Shale		4205
Lime		4330
Lime & Shale		4430
Lime & Chert		4541
Lime		4635
Lime & Arbuckle		4715
Total Depth		4715

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: Wm. Herbert

SUBSCRIBED AND SWORN to before me this 22nd day of December, 1952.

My commission expires June 4, 1955 Marian M. Herbert
Notary Public

PLUGGING			
FILE	SEC 27	T 6	R 29W
BOOK	PAGE 26	LINE 30	

8-16-57
DIVISION
Kansas