

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02853-00-00
Spot: NESWSE Sec/Twnshp/Rge: 30-14S-14W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: RUSCH Well #: 2
County: RUSSELL Total Vertical Depth: 3204 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3203	0	w/200 sxs cmt
SURF	8.625	610	0	w/300 sxs cmt

#104¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/03/2005 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/03/2005 5:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls through tubing at 3150'.
POOH. Shot off 5 1/2" at 1780'.
Pulled to 1411' and pumped 100 sxs cement with 300# hulls.
Pulled to 820' and pumped 40 sxs cement with 100# hulls.
Pulled to 360' and pumped 30 sxs cement with 100# hulls.
Pulled to 168' and circulated with 30 sxs cement.

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

INVOICED

DATE 8-22-05
OR. NO. 2006060345

Form CP-2/3

AUG 12 2005

