

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23450-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 3-17S-12W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: STUMPS B Well #: 1
County: BARTON Total Vertical Depth: 3317 feet

Operator License No.: 3309
Op Name: EAGLE PETROLEUM, INC.
Address: PO BOX 106
BUSHTON, KS 67427

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3311	0	w/125 sxs cmt
SURF	8.625	322	0	w/175 sxs cmt

#10780

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2005 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 10% gel - 1000# hulls.
Solid bridge at 870'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2005 1:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 750'. Allied rigged to tubing and pumped 150 sxs 60/40 pozmix, followed with 150 sxs 60/40 pozmix with 500# hulls mixed in.
Pulled tubing to 450' - pumped 15 sxs 60/40 pozmix to circulate cement out of 5 1/2" casing.
Pulled tubing and pumped 20 sxs 60/40 pozmix to circulate cement out of 8 5/8" casing.
Shut in valve on 8 5/8" casing. Pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3111	3317		

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #17966.

Plugged through: TBG

District: 04

107

Signed: [Signature]
(TECHNICIAN)

INVOICED

DATE 8-22-05

INV. NO 2006060348

AUG 17 2005

BROUGHER OIL, INC.

P. O. DRAWER 1367
GREAT BEND, KS 67530


#1 "B" STUMPS

3-17-12W
SW NW SW

CONTR MOHAWK DRILLING, INC. CTY BARTON

GEOL _____ FIELD ODIN

ELV 1856 KB SPD 3/29/84 CARD ISSUED 5/31/84 IP P 65 BO & 300 BWPD
1846 GL ARB OH 3311-3317



LOG	Tops	Depth/Datum	
			API 15-009-23,450
ANH	738	+1118	8 5/8 " 322 / 175SX; 5 1/2 " 3311 / 125SX
B/ANH	763	+1093	DST (1) 2946-3003 (TOR, DOUG) / 45-15-15-15, REC 5' DM, SIP
TOP	2668	- 812	80-50#, FP 40-40 / 40-40#, HP 1549-1549#, BHT 93°
HEEB	2950	-1094	DST (2) 3214-3256 (LKC) / 45-30-15-30, REC 15' WTRY MUD,
TOR	2969	-1113	W/OIL SPKS, SIP 120-80#, FP 30-30 / 30-30#, BHT 97°
DOUG	2980	-1124	DST (3) 3296-3317 (LKC, ARB) / 30-30-30-30, REC 2220' CL
BR LM	3043	-1187	OIL, 300' SW, SIP 1094-1094#, FP 180-916 / 936-1055#, HP
LANS A	3062	-1206	1747-1707#, BHT 103°
BKC	3301	-1445	MICT - CO. (ARB OH) SWB DWN, GSO, NAT, POP, P 65 BO &
ERO ARB	3311	-1455	300 BWPD, 4/23/84
ARB	3315	-1459	
LTD	3316	-1460	
RTD	3317	-1461	

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INDEXED