

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05492-00-00
Spot: SESESW Sec/Twnshp/Rge: 27-15S-12W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BROWN B Well #: 1
County: RUSSELL Total Vertical Depth: 3264 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3260	0	
SURF	8.625	148	0	

08
\$106

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2005 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2005 4:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran 1" tubing on end of 2 3/8" and stacked out at 770'.
Pumped 150 sxs cement - had some water circulating but no cement.
Pulled tubing - removed 1" and ran 2 3/8" to 558'.
Mixed 95 sxs cement with cement circulating to surface.
Pulled tubing - tied onto production casing - pumped 60 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Tied onto annulus and pumped 35 sxs cement.
Max. P.S.I. 500# and held.

Perfs:

Top	Bot	Thru	Comments
3168	3177		
2988	2992		

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #16459.

Plugged through: TBG

District: 04

Signed _____

Case Morris
(TECHNICIAN)

INVOICED

DATE 8-22-05
INV. NO. 2006060353

AUG 12 2005

