

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06026-00-00
Spot: SWSESE Sec/Twnshp/Rge: 16-14S-14W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: HORACE FINK Well #: 3
County: RUSSELL Total Vertical Depth: 3306 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3306	0	150 SX CMT
SURF	10.75	886	0	400 SX CMT

#10745

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2005 1:30 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2005 6:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3100' and pumped 50 sxs 60/40 pozmix - 10% gel cement with 200# hulls.
Shot off casing at 1546'.
Pulled to 1510' - pumped 200 sxs cement with 300# hulls.
Pulled to 910' - pumped 25 sxs cement with 100# hulls.
Pulled to 610' - pumped 100 sxs cement with 100# hulls.
Pulled to 190' - circulated with 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3290	3298		
3282	3287		
3203	3208		
3142	3451		
3138	3142		
3124	3130		
3071	3082		
3060	3068		
3042	3052		
2928	2938		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 8-24-05
INV. NO. 2006060366

RECEIVED
AUG 24 2005
KCC WICHITA

AUG 18 2005

COOPERATIVE REFG ASS'N #3

FINK

16-11-11W
SW SE SE

RUSSELL

County

Contr.

E 1887 Comm. 7-22-47 Comp. 9-26-47 IP 35 BOPD & 75 % W

Tops	Depth	Datum
ANHY	875	
TOP	2767	
DODGE	2998	
LANS	3030	
B SD	3285	
PRE CAM	3300	
TD	3306	

Casing

10" 890
5" 3306

Perf 12/3294-98, 12/
3290-95, 12/3282-87;
PB 3220, Perf 23/3202-
08, Plug 3190; Perf
24/3138-42, A/2000;
SWB 84 BO & 84 BW/24 hr

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

+	+	+
+	+	+
+	+	+