

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20161-00-00
Spot: NENENE Sec/Twnshp/Rge: 13-5S-22W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: BITTEL Well #: 2
County: NORTON Total Vertical Depth: 3510 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3506	0	w/125 sxs cmt
SURF	8.625	275	0	w/200 sxs cmt

114⁰⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2005 4:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 250 sxs Swift Multi-Density Cement and 500# hulls.
Tubing stuck at 2705'.
08/30/2004- squeezed 2681'-2870' w/200 sxs. Squeeze job didn't hold pumping under packer.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2005 8:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Tubing and packer stuck at 2705'. Backed off packer at 2705'.
Swift pumped 15 sxs at 1900#. Shut down PTOH.
Ran back to 1700'. Swift pumped 65 sxs SMD with 150# hulls cwc.
PTOH. Swift pumped 75 sxs SMD with 350# hulls down 4 1/2" casing.
Max. P.S.I. 1000#. S.I.P. 250#.
Hooked up to 8 5/8" - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3506	3510	OH	

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 8-24-05
INV. NO. 2006060372

RECEIVED
AUG 24 2005
KCC WICHITA

AUG 23 2005

R P NIXON OPERATIONS
 207 W 12TH ST
 HAYS, KS 67601

#2 BITTEL

13-5-22W
 NE NE NE

CONTR ABERCROMBIE DRILLING INC CTY NORTON

GEOL DAN NIXON FIELD DENSMORE EAST

E 2080 KB CM 1/5/80 CARD ISSUED 5/1/80 IP P 15 BOPD

REAG OH 3506-3510

+	+	+
+	+	+

API 15-137-20,161

SMP	TOPS	DEPTH	DATUM
ANH		1680	+ 400
B ANH		1710	+ 370
NO TOPS RELEASED			
RTD		3510	-1430
NO LOG			

8-5/8" 275/200sx, 4 1/2" 3506/125sx

NO DST'S
 MICT - CO, (REAG OH), ONFU 975' OIL
 W/TR WTR, SWB 3.64 BFPH, POP, P 15
 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

NIXON