

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21147-00-00
Spot: NENWSE Sec/Twnshp/Rge: 22-17S-10W
2570 feet from S Section Line, 1780 feet from E Section Line
Lease Name: TRITSCH SCHEPMANN Well #: 1-22
County: ELLSWORTH Total Vertical Depth: 3400 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	459		

#110⁵⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/10/2005 7:00 AM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN COX Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed Plugging Method: 35 sacks of cement at top of Arbuckle; pull drill pipe to 1300' and pump 35 sacks of cement; pull to 975' and pump 35 sacks of cement; pull to 510' and pump 35 sacks of cement; pull to 60' and circulate cement to surface; 15 sacks of cement in rathole; and 10 sacks of cement in mousehole.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 08/10/2005 9:20 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Pumped 35 sacks of cement at 3300' through drill pipe. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 975' and pumped 35 sacks of cement. Pulled to 510' and pumped 35 sacks of cement. Pulled to 60' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #17586

Perfs:

RECEIVED
KCC DISTRICT #2
AUG 10 2005
WICHITA, KS

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 8-22-05
INV. NO 2006060350