

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25438-00-00
Spot: NWSENE Sec/Twnshp/Rge: 3-15S-18W
980 feet from N Section Line, 525 feet from E Section Line
Lease Name: ERNIE ENGEL Well #: 1
County: ELLIS Total Vertical Depth: 3685 feet

Operator License No.: 8729
Op Name: HERTEL, ALBINUS F. DBA HERTEL OIL
Address: 704 E. 12TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		

11976

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/11/2005 10:00 AM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES Witness Type: NONE
Date/Time Plugging Completed: 08/11/2005 11:15 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 3635' w/25 sxs.
2nd. Plug at 1230' w/25 sxs.
3rd. Plug at 514' w/100 sxs.
4th. Plug at 271' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Total of 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

Perfs:

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Regu L Moses
(TECHNICIAN)

INVOICED
DATE 8-22-05
INV. NO. 2006060351

Form CP-2/3

AUG 17 2005