

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21535-00-00
Spot: S2NENESE Sec/Twnshp/Rge: 6-18S-9W
2110 feet from S Section Line, 330 feet from E Section Line
Lease Name: HABIGER Well #: 1
County: RICE Total Vertical Depth: 3243 feet

Operator License No.: 31504
Op Name: STRUBE, KURT J. DBA K.J.S. OIL
Address: 608 WEST PARK STR.
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3240		150 SX CMT
SURF	8.625	298		210 SX CMT

#10540

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/03/2005 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand open hole to 3190' and cap with 5 sacks of cement. Cut off casing; pull to 1200'; and pump 35 sacks of cement. Pull to 850' and pump 35 sacks of cement. Pull to 350' and circulate cement to surface.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL
Date/Time Plugging Completed: 08/03/2005 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3190' and capped with 5 sacks of cement. Cut off casing at 1300'. Pulled to 1200' and pumped 35 sacks of cement. Pulled to 850' and pumped 35 sacks of cement. Pulled to 350' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #17555

Perfs:

Top	Bot	Thru	Comments
3240	3243		

RECEIVED
KCC DISTRICT #2
AUG 10 2005
WICHITA, KS

RECEIVED
AUG 22 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 8-22-05
INV. NO 2006060357