

7-10 266P

6 070931

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22,644-00-00
App. 110'N
SE SE SE, SEC. 31, T 7 S, R 24 WE

440 feet from S section line
250 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30650

Lease Name J&J Goddard Well # 1 31
County Graham 128.37

Operator: Long Run Oil Company P.S.
Name & Address Rural Route 1
P.O. Box 122

Well Total Depth 3950 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 211'

Norcatour, Kansas 67653
Douglas C. Frickey
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Golden Eagle Drilling Inc. License Number 8682

Address McCook, Nebraska

Company to plug at: Hour: A.M. Day: _____ Month: _____ Year: 19

Plugging proposal received from Dave Paschall

(company name) Golden Eagle Drilling (phone) 303-232-9572

were: 8 5/8" - 211' S.P. cir. w/165 sx. 60/40 pozmix - 2% gel. - 3% Ca.Cl. (By Halco)

K.C. Well - Elev. 2422 - Anhy. 2113 - Mud condition 45 vis. - 9.0 wt. - 10 W.L.

Proposal 225 sx. 60/40 pozmix - 6% gel. - 3% Ca.Cl. Spot with drill stem - cir. hole.

Heavy mud between all plugs. 25 sx. @ 2120' - 100 sx. w/1 sx. F.C. @ 1270'. 40 sx.

@ 260' - 10 sx. @ 40' - 15 sx. in rathole (Circulated) 10sx. in mousehole (Circulated)

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN) *MS*

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:30P.M. Day: 10 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Long Run ordered 200 sx. 60/40 pozmix - 6% gel. No arbuckle.

Circulated hole - spotted cement with drill stem, with heavy mud between all plugs.

1st plug @ 2120' w/25 sx. cmt. 4th plug @ 40' w/10 sx. cmt.

2nd plug @ 1270' w/100 sx. cmt. w/1 sx. flocele. 15 sx. Rathole (cir.)

3rd plug @ 260' w/40 sx. cmt. 10 sx. Mousehole (cir.)

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1991
JUL 30 1991

Remarks: By: Halliburton Cement.

(If additional description is necessary, use BACK of this form.)

INVOICED

XXXXX did not observe this plugging.

DATE 8-12-91

INV. NO. 32684

SEP 27 1991

Signed Marion J. Schmidt
(TECHNICIAN)