

6 030978

10-15-87

API NUMBER 15- 065-21,052 -06-00

C SW NE, SE SEC. 31, T 7 S, R 24 W 1/4

1650 feet from S section line

990 feet from E section line

Lease Name Cummings Well # 2 - 31 SWD

County Graham 69.23

Well Total Depth 2130 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 337

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis Corp

Name & Address Box 247

Wichita, Kansas 67201

Abandoned Oil Well Gas Well Input Well SWD Well X U&A

Other well as hereinafter indicated Docket No. C-19,455 CD 10, 784

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: PM Day: 15 Month: Oct. Year: 19 87

Plugging proposal received from Ronnis

(company name) Kelso Casing (phone)

were: 8 5/8" set at 337' w/200 sks 4 1/2" set at 2130' w/550 sks cwc. PBTD 2097'

Perf 1650' - 1866'. Order 160 sks ATL 65/35 Poz 10% Gel 2% Dical Cement Blend.

Allied Cement Co. Joe Neuman Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00PM Day: 15 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/160 sks ATL Cement Blend.

Max Psi 800# Close in Psi 300#. 8 5/8" - 4 1/2" annulus had cement at surface.

Pressured to 500# Psi. Plug complete.

RECEIVED STATE CORPORATION COMMISSION NOV 30 1987

CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Signed Carl Goodrow (TECHNICIAN)

DATE 12-4-87

INV. NO. 19104

Carl Goodrow