

To: 6 030977  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-15-87  
API NUMBER 15- 065-20,914-00-00  
C NE SE, S 31, T 7 S, R 24 (W)  
990 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Operator: Graham Michaelis Corp  
Name & Address Box 247  
Wichita, Kansas 67201

Lease Name Cummings Well # 1-31  
County Graham 135.63  
Well Total Depth 4170 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 235

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: \_\_\_\_\_ PM Day: 15 Month: Oct. Year: 19 87

Plugging proposal received from Ronnis

(company name) Kelso Casing (phone) \_\_\_\_\_

were: 8 5/8" set at 235' w/175 sks. 4 1/2" set at 3967' w/150 sks. Perf. 3786' - 3846'

Order sand and Common Cement. Pull pipe. Order 200 sks ATL 65/35 Poz 10% Gel 2% Dical

Cement Blend 8 sks Hulls. Allied Cement Co. Joe Newman Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:00PM Day: 15 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand Bottom to 3730' w/4 sks Common Cement on sand w/bailer.

Shots at 2200' 1800' 1600' and 812'. Recovered 812' of 4 1/2" casing. Squeeze 4 1/2" casing w/200 sks Cement Blend w/8 sks Hulls mixed in.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify to observe this plugging.

DATE 12-4-87

INV. NO. 19103

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

NOV 30 1987  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS