

6 031138

7-8

API NUMBER 15-065-00587-00-105-106-101

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 32 33, 7 S, R 24 W/E
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Nana NW Well # Unit 201W

Operator: Oxy USA Inc
Name & Address 3545 NW 58th St.
Oklahoma City, Ok. 73112

County Graham 127.89

Well Total Depth 3935 3935 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: August Month: 7 Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 223' w/160 sks cwc. 4 1/2" set at 3934' w/125 sks.

PBTD 3935'. Perfs 3838' - 77'. Shots in Anhy 2050' and below Dakota at 1200'. Order

300 sks Cement Blend w/1/2# Celloflake mixed in and 600# Hulls. Allied Cement Co.

Wellbrock, Hensley Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:45PM Day: 8 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 8 5/8" w/200 sks Cement Blend w/500# Hulls

mixed in last 100 sks to max Psi 800#. Close in Psi 400#. Squeezed 8 5/8" 2/75 sks

cement and 100# Hulls to Max Psi 300#. Close in Psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1988
SEP 16 1988

Remarks: (If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

DATE 9-24-88

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

INV. NO. 22313