

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,639-0000 R

NW, Sec. 27, T 6 S, R 30 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
SEE BELOW

Operator License # _____

Lease Name MORGAN Well # 2A-27

Operator: ALPAR RESOURCES INC.

County SHERIDAN

Name & Address Box 1046

Well Total Depth 4431 feet 8144.01

PERRYTON TEXAS 79070

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor SARGENT'S CASING PULLING License Number 837 (6547)

Address 620 S. LINCOLN BOX 506 LIBERAL, KANSAS

Company to plug at: Hour: AM Day: 11 Month: 6 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BOB SARGENT

(company name) SARGENT'S CASING PULLING (phone) _____

were: BOTTOM PLUG - PUMP WIPER PLUG BEHIND 60 SX.

COM. CEM. TO 2700 - SHOOT - PULL PIPE

SHOTS AT 1800' - 1500' - 1400'

RECOVERED 1400' 4 1/2 CASING

Signed Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 PM Day: 11 Month: 6 Year: 19 83

ACTUAL PLUGGING REPORT BOTTOM PLUG AS ABOVE

TOP PLUG - SQUEEZED DOWN 8 5/8 WITH 2 SX HULLS

20 SX. GEL. 100 SX CEM. 20 SX. GEL - 8 5/8 WIPER PLUG

70 SX. CEM.

CEM > 50/50 POZ 6% GEL. 3% CC

Remarks: MAX. 400'

SHUT IN 200'

TOP DK 1500 BASE 1800

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1983

6-27-83
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.
DATE 7-7-83
INV. NO. 4729-W

Signed Carl Goodnow
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

ALPAR DRILLED A FEW WELLS IN KANSAS THE WINTER OF '81 - '82 AND THIS ONE IS THE ONLY ONE THEY TRIED TO COMPLETE. DUE TO AN IRRIGATED CORN CROP IN '82 AND A LONG WET WINTER OF '83 THEY COULDN'T PLUG THIS WELL TILL NOW. THEIR ACTIVITY IN KANSAS WAS BEFORE OPERATOR LICENSING AND THEY KNEW NOTHING ABOUT IT. THEY WILL, HOWEVER, NOW OBTAIN A LICENSE FOR POSSIBLE FUTURE WORK. THEY HAVE NO OTHER ACTIVITY IN KANSAS AT THIS TIME.