

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19143-00-00
Spot: NWSE Sec/Twnshp/Rge: 5-14S-15W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: M DORTLAND Well #: O-21
County: RUSSELL Total Vertical Depth: 3287 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3285	0	w/250 sxs cmt
SURF	8.625	256	0	w/150 sxs cmt

A/106 83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed
Plugging
Method:

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2005 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 960' and 1350'.
Ran tubing to 3000' - pumped 110 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled to 1550' - pumped 120 sxs cement.
Pulled to 600' - circulated with 25 sxs cement.
Tied onto casing and pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Had cement in annulus.
Had casing leak at approximately 430'.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Case Morris*

(TECHNICIAN)
RECEIVED
AUG 24 2005
KCC WICHITA

INVOICED
DATE 8-24-05
INV. NO. 2006060370

AUG 22 2005