

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21089-00-01
Spot: S2N2NE Sec/Twnshp/Rge: 15-17S-29W
1100 feet from N Section Line, 1230 feet from E Section Line
Lease Name: SNIDER A Well #: 1-15
County: LANE Total Vertical Depth: 4640 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4360 | | |
| PROD | 4.5 | 4639 | 0 | |
| SURF | 8.625 | 347 | | WITH 190 SX CMT |

\$150⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/08/2005 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE Company: SWIFT SERVICES Phone: (785) 798-2300

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS. PULL TUBING TO 1265'. CIRCULATE CMT TO SURFACE FROM 1265'. TOP OFF 4 1/2". CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2005 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

PUMP 30 SX CMT & 200# HULLS AT 4222' THROUGH TUBING. PULL TUBING TO 1265'. CIRCULATE CMT FROM 1265' TO SURFACE WITH 95 SX CMT. TOOH WITH TUBING. TOP OFF 4 1/2" CASING WITH 20 SX CMT. STAYED FULL. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS. PUMP 5 SX CMT AND PRESSURE TO 500#. HELD.


INVOICED

DATE 8-24-05
OFF. NO. 2006060365

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 0



Signed

Ken Jehlik

(TECHNICIAN)

RECEIVED
AUG 24 2005
KCC WICHITA

Form CP-273