

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21349-00-00  
Spot: E2SWSWNE Sec/Twnshp/Rge: 15-17S-29W  
2970 feet from S Section Line, 2210 feet from E Section Line  
Lease Name: SNIDER A Well #: 2-15  
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4580	0	WITH 200 SX CMT
SURF	8.625	354		WITH 190 SX CMT

*#14950*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2005 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: WAYNE WILSON Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SPOT 200# HULLS & 30 SX CMT THROUGH TUBING OR SET CIBP & 25 SX CMT. SPOT PLUG AT 2200' WITH 25 SX CMT. LET PLUG SET & TAG. PERFORATE AT 1250'. PUMP OR SPOT 80 SX CMT OVER CAPACITY OF 5 1/2". IF DOES NOT CIRCULATE PUMP 175 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2005 6:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CEMENTED FROM 100' TO 2300'. PUMPED 30 SX COMMON W/3% CC TO 4033' WITH TUBING. PULLED TUBING TO 1750' & PUMPED 50 SX COMMON CMT WITH 3% CC. WAITED 1 1/2 HOURS. PULLED TUBING TO 1250'. CASING WAS ALREADY PERFORATED AT 1250'. PUMPED 175 SX CMT. DID NOT GET CIRCULATION. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 600# & HELD. PULLED TUBING & WAITED 4 HOURS. TOPPED OFF WITH 50 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4510	4518		
4481	4486		
4433	4435		
4114	4116		

INVOICED  
DATE 8-24-05  
INV. NO 2006060365

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT WITH 3% CC BY SWIFT SERVICES.

Plugged through: TBG

District: 01



Signed Michael J Maier  
(TECHNICIAN)

RECEIVED  
AUG 24 2005  
KCC WICHITA

Form C-106 *[Signature]*