

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05600-00-01  
Spot: SWSWNE Sec/Twnshp/Rge: 8-11S-17W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GILBERT OWWO Well #: 1  
County: ELLIS Total Vertical Depth: 2500 feet

Operator License No.: 8925  
Op Name: LIBERTY OPER & COMPL, INC  
Address: 308 W MILL  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	168	0	w/125 sxs cmt
PROD	5.5	2215	0	w/25 sxs cmt
SURF	8.625	1117	0	w/875 sxs cmt

*8125*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2005 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: CHARLIE FARR Company: LIBERTY OPER & COMPL, INC. Phone: (785) 434-4686

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel - 700# hulls.  
Well plugged 08/01/1964. Recovered 2215' of 5 1/2" casing.  
Re-entered and back in side of 5 1/2" casing to 2500'.  
Ran oversize nipple on new 5 1/2" casing, set at 2215' - cemented with 25 sxs.  
Upon drilling out insert on bottom of 5 1/2" casing, found casing collapsed at 2280'.  
Decided to P/A. Shot casing off at 2179' and laid out - hole full of drilling mud.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/22/2005 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report: Ran 2 3/8" tubing to 2200'. Allied pumped 25 sxs cement with 100# hulls.  
Pulled tubing to 1150'. Allied pumped 25 sxs cement with 150# hulls.  
Pulled tubing to 575'. Allied pumped 50 sxs cement with 200# hulls.  
Pulled tubing to 150'. Allied pumped 50 sxs cement with 250# hulls, filled cellar with cement.  
PTOH. Hole full of cement.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: TBG

District: 04

Signed Richard Williams

**INVOICED**  
DATE 8-24-05  
INV. NO 2006060375  
**RECEIVED**  
AUG 24 2005  
KCC WICHITA

AUG 23 2005

LIBERTY OPERATIONS & COMPLETIONS  
PLAINVILLE KS 67663

8-11S-17W  
SW SW NE

#1 GILBERT OWWO

Size 5-1/4 S 3-1/2 W OF CODELL KS  
CONTR. CHITOS WELL SVC  
BY: ELLIS  
FIELD BEMIS-SHUTTS  
APR 15-051-05600


IP date 04/02/2004  
SPC date 04/05/2004  
DRG COMP 05/01/2004  
CARD ISSUED 11/29/2004  
LAST REVISION 11/29/2004

E.L.V: 1861 KB, 1856 GL LOG	
tops	depth/datum
ANH	1107 +754
*B/ANH	1145 +716
TOP	2810 -949
HEEB	3038 -1177
TOR	3057 -1196
LANS	3079 -1218
CONG	3340 -1479
*SMP DOL	3385 -1524
*SMP SH	3396 -1535
ARB	3409 -1548
RTD OLD	3412 -1551
DDTD OLD	3414 -1553
LTD OLD	3416 -1555

IP status  
TEMP ABD, 06/01/2004  
\*SAMPLE TOP  
OLD INFO: OPERATOR WAS LARIO OIL & GAS CO, 1 GILBERT, SPD 10/20/1951, 11/06/1951 13-3/8" 167.98 / 125 SX, 8-5/8" 1116.95 / 875 SX (ALT 1), 5-1/2" 3412 / 150 SX, OIL, P 2,696 BOPD, NW, ARB 3412-3416, 12/01/1951(CARD ISSUED 12/07/1951)  
CONTR: STEARNS DRILLING  
COMMENT: WAS TEMP AR IOG-460  
SHOWS: 2838-2841 (TOP LM, SO), 2843-2846 (TOP LM, SO), 3094-3101 (LANS LM, SO)

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

LIBERTY OPERATIONS & COMPLETIONS  
PLAINVILLE KS 67663

8-11S-17W  
SW SW NE

#1 GILBERT OWWO

DRLR SD ZNS 30-120 (W/CLAY), 410-585, 590-705  
SALT ZN: 1385-1630 (W/SH), 1630-1705 (W/SH & SHELLS)  
NO CORES

DST (1) 2995-3005 (TOP), / 45-30-0-0, REC 310' SW, W/SLI SO, REMARK: FP NA ISP 50#  
DST (2) 3044-3072 (TOR), / 60-30-0-0, REC 10' M, W/GSO, REMARK: FP NA ISP 1070#  
DST (3) 3069-3101 (LANS), / 30-60-0-0, REC 15' OCM, REMARK: FP NA ISP 0#  
DST (4) 3103-3154 (LKC), / 75-30-0-0, REC 31' OCM, REMARK: FP NA ISP 0#  
DST (5) 3160-3205 (LKC), / 30-30-0-0, REC 443' TF: 40' MDY OIL, 413' MCO, REMARK: FP NA ISP 890#  
DST (6) 3406-3412 (ARB), / 60-30-0-0, REC 18' VHOCM, REMARK: PRESSURES NA  
MICT - CO TO 3413, (ARB OH), BAIL DWN, NS, DD 3416 TD (LTD), BAIL 2 GOPH, NAT, AC 250 GAL, SWB 2 BOPH/12 HRS, RE-AC 750 GAL, SWB LD, SWB 127 BO/2 HRS, POP, IFP 2696 BOPD, NW (DRAW DWN), 12/1/1951 (WELL P & A 8/1/1964)  
NEW INFO: FR 04/02/2004, RE-ENTERED 04/05/2004 WSH DWN DC 05/01/2004 CSG: 5-1/2" CSG SET  
COMMENT: KCC APR 15-051-05600-0001; WELL DRLD W/CABLE TOOL  
TRGT ZN: ARB (OIL), PTD 3413 (ARB), PROBLEMS ENCNTD IN HOLE, S.D. OPERS - EVAL FOR P & A; TEMP ABD 6/1/2004 - NO OTHER INFO AVAILABLE - TEMP COMP 11/29/2004

LARIO OIL & GAS

#1 GILBERT

8-11-17W 37  
SW SW NE

Contr. STEARNS PETROLEUM

ELLIS

County

E 1860RB Comm

Comp. 12-7-51

IP 2696 BOPD

DRAW DOWN

Tops	Depth	Datum
ANH	1107	753
TOP	2810	-950
HEEB	3038	-1178
TOR	3057	-1197
LANS	3079	-1219
CONG	3340	-1480
ARB	3409	-1549
T.D.	3414	-1554

Casing  
12" 160  
SSO 2838-41, 2843-46  
DST 2995-3005, 45 MIN, 310'  
S WTR: SSO: BHP 50#  
DST 3044-72, 1 HR; 10' MUO  
BHP 1070#; GSO 3094-3101  
DST 3069-3101, 1 HR, 15' OIL  
CUT MUO: BHP 0#; DST 3103-54, 75 MIN, 31' OIL CUT MUO  
BHP 0#; DST 3160-3205, 30 MIN; 40' MUO OIL, 413'  
CUT OIL: BHP 890#; DST 3406-12-1 HR, 18' V H  
BURNETT EAST POOL OIL CUT MUO: BAILING  
HOLE: DP: CO 3413: NS: DD 3414: BAIL 2 GOPH: ACID 250 SWB 2 BOPH/12 HRS: ACID 750 SWB 127 BO/2 HRS: POP


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS