

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22309-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 9-17S-11W  
3630 feet from S Section Line, 330 feet from W Section Line  
Lease Name: HAROLD GROSSHARDT Well #: 4  
County: BARTON Total Vertical Depth: 3315 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3310	0	100 SX CMT
SURF	8.625	247	0	150 SX CMT

#107 74

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2005 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: VESS OIL CORPORATION Phone: (316) 215-1873

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2005 11:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Could not get past 816'.  
Perforated at 670'.  
Ran tubing to 810'.  
Circulated with 95 sxs 60/40 pozmix - 10% gel cement.  
POOH.  
Pumped 155 sxs cement down casing.  
Max. P.S.I. 600#. S.I.P. 200#.  
Pumped 30 sxs down backside.  
Max. P.S.I. 400# S.I.P. 200#

Perfs:

Top	Bot	Thru	Comments
3310	3315		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

FD

Signed

Case Morris

(TECHNICIAN)

**INVOICED**

**RECEIVED**

DATE

8-24-05

AUG 24 2005

INV. NO.

2006060384

KCC WICHITA

AUG 22 2005

~~WICHITA~~  
~~WICHITA~~

**INVOICED**

PETROLEUM ENERGY INC #4 GROSSARDT "A" 9-17-11W  
 710 ONE TWENTY BLDG. NW SW NW  
 WICHITA, KS 67202  
 CONTR ALLEN DRILG. CO. CTY BARTON

GEOL \_\_\_\_\_ FIELD KRAFT-PRUSA

E 1855 KB CM 4/15/81 CARD ISSUED 6/25/81 IP P 10 BOPD NW  
 ARB OH 3310-3315

+	+	+
+	+	+
+	+	+

API 15-009-22,309

SMP	TOPS	DEPTH	DATUM
HEEB	2914	-1059	
TOR	2931	-1076	
DOUG	2947	-1092	
BR LM	3017	-1162	
LANS	3033	-1178	
ARB	3308	-1453	
RTD	3315	-1466	

8-5/8" 247/150sx, 4 1/2" 3310/100sx  
 DST (1) 3285-3312/30-30-30-30, REC  
 1' FO, 5' OCM, SIP 789-756#, FP  
 44-55/66-77#  
 DST (2) 3285-3315/30-30-30-30, REC  
 25' CO, 120' OCM, NW, SIP 778-  
 745#, FP 44-55/66-66#  
 MICT - CO, (ARB OH), FU 900' O, NAT,  
 TSTD, ONFU 580' O & TR WTR, SWB DWN,  
 AC 250 GAL, SWB 4.44 BFPH (21% O &  
 79% AC WTR), POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS