

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04593-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 1-19S-12W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HEINZ B Well #: 1
County: BARTON Total Vertical Depth: 3353 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3410	0	150 SX CMT
SURF	8.625	304	0	200 SX CMT

#108⁹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2005 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CASEY COATS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 682-1537

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2005 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3140' and dumped 5 sxs cement.
Cut off casing at 1816'.
Pulled to 1460' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 710' - pumped 25 sxs cement with 100# hulls.
Pulled to 400' - pumped 40 sxs cement with 100# hulls.
Pulled to 200' - circulated with 45 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3410	3419		
3401	3407		
3321	3325		
3287	3291		
3282	3284		
3261	3265		
3206	3213		
3169	3173		
3147	3151		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Handwritten initials

Handwritten signature

(TECHNICIAN)

INVOICED

DATE 8-24-05

INV. NO. 2006060384

RECEIVED

AUG 24 2005

KCC WICHITA

AUG 18 2005

SOHIO PETROLEUM

#1 HEINZ B

1-19-12W / 53
NW NW SW

Contr. _____ BARTON County

E 1831RD Comm. _____ Comp. 10-26-51 IP 225 BOPD
FLOW POT

Tops	Depth	Datum
TOP	2729	-898
HEEB	2990	-1159
BR LM	3108	-1277
LANS	3119	-1288
T. D.	3353	-1522

Casing
 8" 304
 5" 3407
 -1576

DST 2927-47, 60 MIN, 45'
 MUDDY S WTR: SSO: BHP 640
 DST 3120-31, 60 MIN, 25'
 MUDDY S WTR: SSO & GAS:
 DST 3142-53, 60 MIN, 155'
 HEAVY GAS CUT OIL & 150'
 FREE OIL: BHP 1000
 DP 3416: 6 GOPH: ACID 500:
 DD 3421: ACID 1000: SWB 1
 BOPH: ACID 3000: 3 BOPH:
 PB 3360: PERF 3279-81,
 3284-88: ACID 1000: 6 BOPH
 CHEYENNE VIEW POOL PB 3274:
 PERF 3258-62: 6 BOPH:
 DD 3353: SWB 21 BO, NO WTR/
 24 HRS: PMP 68 BO, NO
 WTR/21 HRS

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED