

4-041796 15-179-20696-0000

9-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number 15
RECEIVED
KANSAS CORP COMM

W2 SE SE /4 SEC. 16, 06 S, 29 W
660 feet from S section line
990 feet from E section line
9-17-96

Operator license# 8847
2947

Lease: Brantley Well # 4

Operator: Hoff Oil & Gas

County: Sheridan 135.03

Address: P.O. Box 49
Selden, Kansas 67757

Well total depth 4155 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 259 feet
w/160 sxs.cmt.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Oakley, Kansas 67725

Company to plug at: Hour: 12:00 P.M. Day 12 Month: September Year 1996

Plugging proposal received from: Elmer Hoff

Company: Hoff Oil & Gas Phone:

Were: 5 1/2" casing set at 4154' w/200 sxs cement. Perf. at 4096' - 4100'.

D.V. - Anhys at 2561' - 2595'. D.V. cwc.

Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - plus 13 sxs gel.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour 1:30 P.M., Day: 9, Month: September, Year: 1996

Actual plugging report: R.U. unit, pulled tubing and rods: R.U. Cementer to 5 1/2" casing.
Squeezed casing as follows: 50 sxs cement with 500# hulls, followed with 13 sxs gel, followed
with 130 sxs cement. Max. P.S.I. 800#. S.I.P 700#. R.U. Cementers to 8 5/8" S.P.
Pressured-up 700#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging.

Dennis J. Hamel
(agent)

INVOICED
DATE 9-20-96
INV. NO. 46530