

4-090513

12-7

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,614-00-00

NE NE SW /4 SEC. 29, 06 S, 31 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5131 Lease Keller Trust well # 1

Operator: Thunderbird Drilling, Inc. County Thomas

Address: P.O. Box 780407 Well total depth 4580 feet  
Wichita, Kansas 67278 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 263 feet

148.85

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 3 Month: December Year: 93

Plugging proposal received from: Gary Fisher

Company: Abercrombie RTD, Inc. Phone: \_\_\_\_\_

Were: Order 190 sxs. 60/40 posmix with 6% gel and 1 sx. celloflake.  
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 7:15A.M., Day: 7, Month: December, Year: 93

Actual plugging report:  
1st. plug at 2670' w/25 sxs.  
2nd. plug at 1830' w/100 sxs.  
3rd. plug at 315' w/40 sxs.  
4th. plug at 40' w/10 sxs.  
15 sxs. in rathole.

Remarks: By: Allied Cementing. No ar buckle.  
Condition of casing(in hole): GOOD BAD Any plug: YES ✓ NO  
Bottom plug(in place): YES CALC, NO X Dakota plug: YES ✓, NO  
Plugged through TUBING CASING. Elevation: 2983 GL

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1993

CONSERVATION DIVISION  
WICHITA, KANSAS

I did not [ X ] observe the plugging.

Ed Schumacher

12-15-93

(agent)

Form CP-2/3

INVOICED

DATE 12-30-93

INV. NO. 39611